

AD-A143 342


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
BRADLEY HUBBARD RESER. (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV SEP 80


1/2

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A143 342

QUINNIPIAC RIVER BASIN
MERIDEN, CONNECTICUT
BRADLEY HUBBARD RESERVOIR DAM
CT 00132

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

SEPTEMBER, 1980

DISTRIBUTION STATEMENT A

Approved for public release;
Distribution Unlimited

DTIC
ELECTE
S JUL 25 1984 **D**
D

DTIC FILE COPY

84 07 24 094

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| REPORT DOCUMENTATION PAGE | | READ INSTRUCTIONS BEFORE COMPLETING FORM |
|---|--|---|
| 1. REPORT NUMBER CT 00132 | 2. GOVT ACCESSION NO. AD 4143 342 | 3. RECIPIENT'S CATALOG NUMBER |
| 4. TITLE (and Subtitle) Bradley Hubbard Reservoir Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS | | 5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT |
| 7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION | | 6. PERFORMING ORG. REPORT NUMBER |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS | | 8. CONTRACT OR GRANT NUMBER(s) |
| 11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254 | | 10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS |
| 14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) | | 12. REPORT DATE September 1980 |
| | | 13. NUMBER OF PAGES 55 |
| | | 15. SECURITY CLASS. (of this report) UNCLASSIFIED |
| | | 15a. DECLASSIFICATION/DOWNGRADING SCHEDULE |
| 16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED | | |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) | | |
| 18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report. | | |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Quinnipiac River Basin Meriden, Conn. Bradley Hubbard Reservoir Dam | | |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The project has a total length of 545 ft. consisting of 340 ft. masonry core with earth fill on the upstream and downstream sides, a 115 ft. long earth embankment at the right end of the dam, and section of concrete corewall at each end. It is classified as a high hazard, small size dam. The test flood range is from one-half to full Probable Maximum Flood. | | |



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02254

REPLY TO
ATTENTION OF:
NEDED-E

JAN 07 1981

Honorable William A. O'Neill
Governor of the State of Connecticut
State Capitol
Hartford, Connecticut 06115

Dear Governor O'Neill:

Inclosed is a copy of the Bradley Hubbard Reservoir Dam (CT-00132) Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. The report is based upon a visual inspection, a review of past performance, and a preliminary hydrological analysis. A brief assessment is included at the beginning of the report.

The preliminary hydrologic analysis has indicated that the spillway capacity for the Bradley Hubbard Reservoir Dam would likely be exceeded by floods greater than 17 percent of the Probable Maximum Flood (PMF), the test flood for spillway adequacy. Our screening criteria specifies that a dam of this class which does not have sufficient spillway capacity to discharge fifty percent of the PMF, should be adjudged as having a seriously inadequate spillway and the dam assessed as unsafe, non-emergency, until more detailed studies prove otherwise or corrective measures are completed.

The term "unsafe" applied to a dam because of an inadequate spillway does not indicate the same degree of emergency as that term would if applied because of structural deficiency. It does indicate, however, that a severe storm may cause overtopping and possible failure of the dam, with significant damage and potential loss of life downstream.

It is recommended that within twelve months from the date of this report the owner of the dam engage the services of a professional or consulting engineer to determine by more sophisticated methods and procedures the magnitude of the spillway deficiency. Based on this determination, appropriate remedial mitigating measures should be designed and completed within 24 months of this date of notification. In the interim a detailed emergency operation plan and warning system should be promptly developed. During periods of unusually heavy precipitation, round-the-clock surveillance should be provided.

NEDED-E

Honorable William A. O'Neill


I have approved the report and support the findings and recommendations described in Section 7, with qualifications as noted above. I request that you keep me informed of the actions taken to implement these recommendations since this follow-up is an important part of the non-Federal Dam Inspection Program.

A copy of this report has been forwarded to the Department of Environmental Protection, the cooperating agency for the State of Connecticut. This report has also been furnished to the owner of the project, City of Meriden, Dept. of Public Works, Meriden, CT.

Copies of this report will be made available to the public, upon request to this office, under the Freedom of Information Act, thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Department of Environmental Protection for the cooperation extended in carrying out this program.

Sincerely,


WILLIAM E. HODGSON, JR.
Colonel, Corps of Engineers
Acting Division Engineer

| | |
|--------------------|--|
| Accession For | |
| NTIS GSA&I | <input checked="checked" type="checkbox"/> |
| DTIC TAB | <input type="checkbox"/> |
| Unannounced | <input type="checkbox"/> |
| Justification | |
| By | |
| Distribution/ | |
| Availability Codes | |
| Dist | Avail and/or Special |
| A/1 | |



QUINNIPIAC RIVER BASIN
MERIDEN, CONNECTICUT
BRADLEY HUBBARD RESERVOIR DAM
CT 00132

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

SEPTEMBER, 1980

BRIEF ASSESSMENT
PHASE I INSPECTION REPORT
NATIONAL PROGRAM OF INSPECTION OF DAMS

| | |
|---------------------|-------------------------------|
| Name of Dam: | BRADLEY HUBBARD RESERVOIR DAM |
| Inventory Number: | CT 00132 |
| State Located: | CONNECTICUT |
| County Located: | NEW HAVEN |
| Stream: | HARBOR BROOK |
| Owner: | CITY OF MERIDEN |
| Date of Inspection: | MAY 12, 1980 |
| Inspection Team: | PETER HEYNEN, P.E. |
| | DR. MURALI ATLURU, P.E. |
| | MIRON PETROVSKY |
| | JAY A. COSTELLO |
| | JEFFREY BORNE |


The project, built about 1891 has a total length of 545 feet consisting of a 340-foot masonry core with earth fill on the upstream and downstream sides, a 115 foot long earth embankment at the right end of the dam, and sections of concrete corewall at each end (See Sheet B-1). A 71 foot broad-crested masonry spillway is located at the central portion of the dam. The top of the dam (elevation 312.0) is 7 feet wide and 16.5 feet above the Harbor Brook streambed. The maximum storage capacity with the pond level to the top of the dam is approximately 216 acre-feet of water. A gatehouse, located upstream and adjacent to the right end of the spillway, contains two valves which regulate a 20 inch blowoff and a 12 inch supply main which once led to the Bradley and Hubbard Corp.

In accordance with the Army Corps of Engineer's Guidelines, Bradley Hubbard Reservoir Dam is classified as a high hazard, small size dam. The test flood range is from one-half to full Probable Maximum Flood (PMF). The selected test flood for Bradley Hubbard Reservoir Dam is equivalent to the PMF. Peak inflow to the reservoir at the test flood is 1500 cubic feet per second (cfs); peak outflow is 1325 cfs with the dam overtopped by 0.9 feet. The spillway capacity with the reservoir level to the top of the dam is 223 cfs, which is equivalent to 17% of the routed test flood outflow.


Based upon the visual inspection at the site and past performance, the project is judged to be in fair condition. There are items which require maintenance and/or evaluation, such as seepage, deteriorated masonry, the presence of animal burrows in the embankments, and the irregularities caused by erosion of the upstream and downstream embankments.

It is recommended that the owner retain the services of a registered professional engineer to analyze in more detail the adequacy of the existing project discharge and overtopping potential. Other items of importance are monitoring of seepage, repair of deteriorated masonry, repair of erosion and replacement of riprap at the right end of the upstream slope, filling of animal burrows, and the development of maintenance procedure and emergency action programs. Recommendations made by the engineer should be implemented by the owner.

The above recommendations and further remedial measures presented in Section 7 should be installed within one year of the owner's receipt of this report.




Peter M. Heynen, P.E.
Project Manager - Geotechnical
Cahn Engineers, Inc.





C. Michael Horton, P.E.
Department Head
Cahn Engineers, Inc.



This Phase I Inspection Report on Bradley Hubbard Reservoir Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.

Carney M. Terzian

CARNEY M. TERZIAN, MEMBER
Design Branch
Engineering Division

Richard J. DiBuono

RICHARD DIBUONO, MEMBER
Water Control Branch
Engineering Division

Aramast Mahtesian

ARAMAST MAHTESIAN, CHAIRMAN
Geotechnical Engineering Branch
Engineering Division

APPROVAL RECOMMENDED:

Joe B. Fryar

JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspection. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam would necessarily represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions will be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

The Phase I Investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with OSHA rules and regulations is also excluded.

The information contained in this report is based on the limited investigation described above and is not warranted to indicate the actual condition of the dam. The integrity of the dam can only be determined by a means of a monitoring program and/or a detailed physical investigation. The accuracy of available data is assumed where not in obvious conflict with facts observable during the visual inspection.

TABLE OF CONTENTS

| | <u>Page</u> |
|-----------------------------|-------------|
| Letter of Transmittal | |
| Brief Assessment | i, ii |
| Review Board Signature Page | iii |
| Preface | iv-v |
| Table of Contents | vi-viii |
| Overview Photo | ix |
| Location Map | x |

SECTION 1: PROJECT INFORMATION

| | |
|---|-----|
| 1.1 <u>General</u> | 1 |
| a. Authority | |
| b. Purpose of Inspection Program | |
| c. Scope of Inspection Program | |
| 1.2 <u>Description of Project</u> | 1-2 |
| a. Location | |
| b. Description of Dam and Appurtenances | |
| c. Size Classification | |
| d. Hazard Classification | |
| e. Ownership | |
| f. Operator | |
| g. Purpose of Dam | |
| h. Design and Construction History | |
| i. Normal Operational Procedures | |
| 1.3 <u>Pertinent Data</u> | 1-3 |
| a. Drainage Area | |
| b. Discharge at Damsite | |
| c. Elevations | |
| d. Reservoir | |
| e. Storage | |
| f. Reservoir Surface | |
| g. Dam | |
| h. Diversion and Regulatory Tunnel | |
| i. Spillway | |
| j. Regulating Outlets | |

SECTION 2: ENGINEERING DATA

| | |
|------------------------------------|-----|
| 2.1 <u>Design Data</u> | 2-1 |
| 2.2 <u>Construction Data</u> | 2-1 |
| 2.3 <u>Operation Data</u> | 2-1 |

TABLE OF CONTENTS

| | <u>Page</u> |
|-----------------------------|-------------|
| Letter of Transmittal | |
| Brief Assessment | i, ii |
| Review Board Signature Page | iii |
| Preface | iv-v |
| Table of Contents | vi-viii |
| Overview Photo | ix |
| Location Map | x |

SECTION 1: PROJECT INFORMATION

| | | |
|-----|---|-----|
| 1.1 | <u>General</u> | 1-1 |
| | a. Authority | |
| | b. Purpose of Inspection Program | |
| | c. Scope of Inspection Program | |
| 1.2 | <u>Description of Project</u> | 1-2 |
| | a. Location | |
| | b. Description of Dam and Appurtenances | |
| | c. Size Classification | |
| | d. Hazard Classification | |
| | e. Ownership | |
| | f. Operator | |
| | g. Purpose of Dam | |
| | h. Design and Construction History | |
| | i. Normal Operational Procedures | |
| 1.3 | <u>Pertinent Data</u> | 1-3 |
| | a. Drainage Area | |
| | b. Discharge at Damsite | |
| | c. Elevations | |
| | d. Reservoir | |
| | e. Storage | |
| | f. Reservoir Surface | |
| | g. Dam | |
| | h. Diversion and Regulatory Tunnel | |
| | i. Spillway | |
| | j. Regulating Outlets | |

SECTION 2: ENGINEERING DATA

| | | |
|-----|--------------------------------|-----|
| 2.1 | <u>Design Data</u> | 2-1 |
| 2.2 | <u>Construction Data</u> | 2-1 |
| 2.3 | <u>Operation Data</u> | 2-1 |

| | | |
|---|---|-----|
| 2.4 | <u>Evaluation Data</u> | 2-1 |
| | a. Availability | |
| | b. Adequacy | |
| | c. Validity | |
| SECTION 3: VISUAL INSPECTION | | |
| 3.1 | <u>Findings</u> | 3-1 |
| | a. General | |
| | b. Dam | |
| | c. Appurtenant Structures | |
| | d. Reservoir Area | |
| | e. Downstream Channel | |
| 3.2 | <u>Evaluation</u> | 3-2 |
| SECTION 4: OPERATIONAL AND MAINTENANCE PROCEDURES | | |
| 4.1 | <u>Operational Procedures</u> | 4-1 |
| | a. General | |
| | b. Description of any Warning System In Effect | |
| 4.2 | <u>Maintenance Procedures</u> | 4-1 |
| | a. General | |
| | b. Operating Facilities | |
| 4.3 | <u>Evaluation</u> | 4-1 |
| SECTION 5: EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES | | |
| 5.1 | <u>General</u> | 5-1 |
| 5.2 | <u>Design Data</u> | 5-1 |
| 5.3 | <u>Experience Data</u> | 5-1 |
| 5.4 | <u>Test Flood Analysis</u> | 5-1 |
| 5.5 | <u>Dam Failure Analysis</u> | 5-1 |
| SECTION 6: EVALUATION OF STRUCTURAL STABILITY | | |
| 6.1 | <u>Visual Observations</u> | 6-1 |
| 6.2 | <u>Design and Construction Data</u> | 6-1 |
| 6.3 | <u>Post Construction Changes</u> | 6-1 |
| 6.4 | <u>Seismic Stability</u> | 6-1 |

SECTION 7: ASSESSMENT, RECOMMENDATIONS & REMEDIAL MEASURES

| | | |
|-----|---|-----|
| 7.1 | <u>Dam Assessment</u> | 7-1 |
| | a. Condition | |
| | b. Adequacy of Information | |
| | c. Urgency | |
| 7.2 | <u>Recommendations</u> | 7-1 |
| 7.3 | <u>Remedial Measures</u> | 7-2 |
| | a. Operation and Maintenance Procedures | |
| 7.4 | <u>Alternatives</u> | 7-2 |

APPENDICES

| | <u>Page</u> |
|---|---------------------------------------|
| APPENDIX A: <u>INSPECTION CHECKLIST</u> | A-1 to A-3 |
| APPENDIX B: <u>ENGINEERING DATA AND CORRESPONDENCE</u> | |
| | Dam Plan, Profile and Sections |
| | Existing Plans |
| | Summary of Data and Correspondence |
| | Data and Correspondence |
| | Sheet B-1 B-1 B-2 B-3 |
| APPENDIX C: <u>DETAIL PHOTOGRAPHS</u> | |
| | Photograph Location Plan |
| | Photographs |
| | Sheet C-1 C-1 to C-3 |
| APPENDIX D: <u>HYDRAULIC/HYDROLOGIC COMPUTATIONS</u> | |
| | Drainage Area Map |
| | Computations |
| | Preliminary Guidance for Estimating |
| | Maximum Probable Discharges |
| | Sheet D-1 D-1 to D-25 i to viii |
| APPENDIX E: <u>INFORMATION AS CONTAINED IN THE</u> <u>NATIONAL INVENTORY OF DAMS</u> | E-1 |




OVERVIEW PHOTO
(February, 1980)

US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS

CAHN ENGINEERS INC.
WALLINGFORD, CONN.
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Bradley Hubbard Res. Dam
Harbor Brook
Meriden, CT
CE # 27 785 KE
DATE Sept. '80 PAGE 1x



LOCATION MAP
CONNECTICUT



PHASE I INSPECTION REPORT
BRADLEY HUBBARD RESERVOIR DAM
SECTION I - PROJECT INFORMATION

1.1 GENERAL

a. Authority - Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Cahn Engineers, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of Connecticut. Authorization and notice to proceed were issued to Cahn Engineers, Inc. under a letter of April 14, 1980 from William E. Hodgson, Jr. Colonel, Corps of Engineers. Contract No. DACW 33-80-C-0052 has been assigned by the Corps of Engineers for this work.

b. Purpose of Inspection Program - The purposes of the program are to:

1. Perform technical inspection and evaluation of non-federal dams to identify conditions requiring correction in a timely manner by non-federal interests.
2. Encourage and prepare the States to quickly initiate effective dam inspection programs for non-federal dam.
3. To update, verify and complete the National Inventory of Dams.

c. Scope of Inspection Program - The scope of this Phase I inspection report includes:

1. Gathering, reviewing and presenting all available data as can be obtained from the owners, previous owners, the state and other associated parties.
2. A field inspection of the facility detailing the visual condition of the dam, embankments and appurtenant structures.
3. Computations concerning the hydraulics and hydrology of the facility and its relationship to the calculated flood through the existing spillway.
4. An assessment of the condition of the facility and corrective measures required.

It should be noted that this report passes judgment only on those factors of safety and stability which can be determined by a visual surface examination. The inspection is to identify those visually apparent features of the dam which evidence the need for corrective action and/or further study and investigation.

1.2 DESCRIPTION OF PROJECT

a. Location - The dam is located on Harbor Brook (Quinnipiac River Basin) in a suburban area of the City of Meriden, County of New Haven, State of Connecticut. The dam is shown on the Meriden USGS Quadrangle Map having coordinates latitude N41°33.5' and longitude W72°45.7'.

b. Description of Dam and Appurtenances - The dam totals more than 545 feet in length and consists of several sections; the original stone masonry section with earth fill added to the upstream and downstream sides, a 115+ foot long earth embankment at the right end of the dam and a concrete corewall at each end of the dam extending into the natural earth abutment. The stone masonry section is 340 feet long and the earth embankment is 115+ feet in length. The original masonry dam was raised 3.5 feet in 1912. At this time the earthfill was added at the upstream and downstream sides of the masonry and the earth embankment section was added to fill a low area at the right end of the dam. A concrete corewall was also added at each end of the dam. At the right end, the corewall abuts the original masonry and extends through the earth embankment to 175 feet from the masonry core. At the left end, a 30 foot section extends into the earth abutment and abuts the original masonry (See Sheet B-1). Raising the original dam consisted of removing the cap stones and placing a 3.5 foot thick section of concrete on the dam and replacing the cap stones, raising the dam 3.5 feet. (See Section B-B, Sheet B-1). The top of the masonry coping (elevation 312.0) is 7.0 feet wide, 1.0 foot above the spillway crest and 16.5 feet above the streambed at the toe of the dam. The top of the earth embankment section is approximately 15 feet wide and at elevation 313.0. The concrete corewall at the right end is 5.0 feet thick and tapers to 2.0 feet thick at the top, which is 1.0 feet below the top of the embankment (See Sheet B-1). The concrete corewall extension at the left end is approximately 5.0 feet thick.

The earth fill at the upstream side of the masonry is inclined at 2.5 horizontal to 1 vertical and is overlain by a rock fill which is inclined at 1.5 horizontal to 1 vertical and extends to 2+ feet from the top of the masonry. A 2.0 foot thick section of concrete extends along the entire length of the upstream face of the masonry core and was placed at the time of the reconstruction (See Section B-B, Sheet B-1). The earthfill on the downstream side of the masonry core is inclined at 2.0 horizontal to 1 vertical and has a grass cover.

The spillway is 71 feet long, located 90 feet from the left abutment and has a crest elevation of 311.0. It is a broad-crested masonry weir of rectangular cross-section with a masonry approach channel and a downstream face of stepped masonry. Extending from the downstream side of the masonry face are stepped masonry wingwalls at each end of the spillway. At the base of the spillway there is a cobble apron.

A brick gatehouse is located upstream and adjacent to the right end of the spillway and accessible by a steel framed footbridge. Two manually operated gate valves are operated from within the gate house. One valve regulates a 20 inch blow-off, which presently acts as a low-level outlet, and the other regulates a 12 inch supply main which once led to the Bradley Hubbard Company, but now is terminated.

c. Size Classification - (SMALL) - The dam impounds 216 acre-feet of water with the reservoir level to the top of the dam, which at elevation 312.0, is 16.5 feet above the streambed of Harbor Brook. According to recommended guidelines, a dam with this height and maximum storage capacity is classified as small in size.

d. Hazard Classification - (HIGH) - If the dam were breached there is potential for loss of more than a few lives and extensive property damage to the George Hunter Golf Course and at least two homes on Westfield Road 3,500 feet downstream from the dam. The golf course is expected to be inundated by 6.6 to 11.0 feet of water in the vicinity of the streambed. At the second impact area, one house located 7.6 feet above the stream would be inundated by 3.4 feet of water and another house located 8.8 feet above the stream would experience up to 2.2 feet of water in the first floor. In addition, it is expected that Westfield Road would experience some flooding.

e. Ownership - City of Meriden
Department of Public Works
City Hall
Meriden, CT 06450
Bruce Marks (Director) (203)-634-0003

f. Operator - Owner (See Ownership, above)

g. Purpose - Originally for water supply, presently used for recreation.

h. Design and Construction History - The following information is believed to be accurate, based on the available data and correspondence and an interview with the owner of the dam. The dam was constructed about 1891 by James Kane and Sons, Builders, to supply water to the downstream factories. The dam was raised 3.5 feet and the 115 foot earth embankment and concrete corewalls were added about 1912. This work was performed by Leonardo Suzio, Contractor. There is no record of repairs or other alterations other than the raising in 1912.

i. Normal Operational Procedures - There are no formal operational procedures followed at the dam. The 20 inch low-level outlet is kept partially open. The 12 inch supply line has been terminated and is not functional.

1.3 PERTINENT DATA

a. Drainage Area - The drainage area is 0.59 square miles of mostly wooded, rolling to mountainous terrain located in the Quinnipiac River Basin. Approximately 8,500 feet upstream from the reservoir, there is a 700-foot long ungated conduit which diverts water into the Bradley Hubbard Reservoir and significantly enlarges the drainage area.

b. Discharge at Damsite - Discharge is over the spillway and through the 20 inch low-level outlet.

1. Outlet Works:

20 inch low-level outlet
invert el. Not known

40 cfs (pond level at
top of dam)

12 inch supply main:

N/A

2. Maximum flood at damsite:

Unknown

3. Ungated spillway capacity
@ top of dam el. 312.0:

223 cfs

4. Ungated spillway capacity
@ test flood el. 312.9:

604 cfs

5. Gated spillway capacity
@ normal pool:

N/A

6. Gated spillway capacity
@ test flood:

N/A

7. Total spillway capacity
@ test flood el. 312.9:

604 cfs

8. Total project discharge
@ test flood el. 312.9:

1325 cfs

c. Elevations - (NGVD based on assumed spillway elevation,
See Sheet B-1).

1. Streambed at toe of dam:

295.5± ft.

2. Bottom of cutoff:

N/A

3. Maximum tailwater:

N/A

4. Normal pool:

311.0 ft.

5. Full flood control pool:

N/A

6. Spillway crest (ungated):

311.0 ft.

7. Design surcharge (original design): Not known
8. Top of dam: 312.0 ft. (masonry)
313.0 ft. (embankment)
9. Test flood surcharge: 312.9 ft.
- d. Reservoir Length (feet)
 1. Normal pool: 3340 ft.
 2. Flood control pool: N/A
 3. Spillway crest pool: 3340 ft.
 4. Top of dam pool: 3400 ft.
 5. Test flood pool: 3440 ft.
- e. Reservoir Storage (acre-feet)
 1. Normal pool: 180 acre-ft.
 2. Flood control pool: N/A
 3. Spillway crest pool: 180 acre-ft.
 4. Top of dam pool: 216 acre-ft.
 5. Test flood pool: 230 acre-ft.
- f. Reservoir Surface (acres)
 1. Normal pool: 35 acres
 2. Flood control pool: N/A
 3. Spillway crest pool: 35 acres
 4. Top of dam pool: 35.8 acres
 5. Test flood pool: 36 acres.
- g. Dam
 1. Type: masonry core section with earth embankment slopes
 2. Length: 340 ft.
 3. Height: 16.5 ft.
 4. Top width: 7.0 ft.

- | | |
|---------------------|--|
| 5. Side slopes: | 1.5H to 1V (upstream) 2.0H to 1V (Downstream) |
| 6. Zoning: | N/A |
| 7. Impervious core: | Masonry core possibly to bedrock |
| 8. Cutoff: | N/A |
| 9. Grout curtain: | N/A |
| 10. Other: | 115 foot long earth embank- ment at right end. A 175 foot long concrete core- wall at right end of masonry and 30 foot long concrete corewall at left end of masonry |

h. Diversion and Regulating Tunnel N/A

i. Spillway

- | | |
|------------------------|---|
| 1. Type: | Broad-crested stone masonry rectangular weir |
| 2. Length of weir: | 71 ft. |
| 3. Crest elevation: | 311.0 ft. |
| 4. Gates: | N/A |
| 5. Upstream channel: | 1.5H to 1V gravel |
| 6. Downstream channel: | original streambed |
| 7. General: | N/A |

j. Regulating Outlets - The outlet is a 20 inch low-level outlet (blow-off). An abandoned 12 inch supply main still extends through the masonry and earth fill section.

- | | |
|-----------------------------|-----------------|
| 1. Invert: Low-level outlet | Unknown |
| Supply main | N/A |
| 2. Size: Low-level outlet | 20 inch |
| Supply main | 12 inch |
| 3. Description: | Cast iron pipes |

4. Control mechanism:

Manually operated handwheel
pedestal, gate valve

5. Other:

Supply main abandoned.
Actual length of pipe or
where it terminates is un-
known.

SECTION 2: ENGINEERING DATA

2.1 DESIGN

Available data consists of a plan accompanied by a contract and specifications between International Silver Co. in partnership with the Bradley and Hubbard Mfg. Co. and Leonardo Suzio, Contractor in reference to the raising of the dam; correspondence concerning an inspection of the dam on June 10, 1965 by John J. Mozzochi and Associates of Glastonbury Ct; and correspondence concerning an inspection of the dam on April 12, 1973 by Buck and Buck Engineers of Hartford, Connecticut. All correspondence is available from the State of Connecticut Department of Environmental Protection. The specifications and plan are available at the Town Hall, Meriden, Connecticut.

The drawings and correspondence indicate the design features stated previously in this report. There were no engineering values, assumptions, test results or calculations available for the original dam design or the 1912 raising of the dam.

2.2 CONSTRUCTION

There is no data available for the original construction of the dam or subsequent raising of the dam in 1912.

2.3 OPERATIONS

No operation records are known to exist.

2.4 EVALUATION

a. Existing Data - Existing data was provided by the State of Connecticut Department of Environmental Protection and the owner. The owner also made the project available for visual inspection.

b. Adequacy - The limited amount of detailed engineering data available was generally inadequate to perform an in-depth assessment of the dam, therefore, the final assessment of this dam must be based primarily on visual inspection, performance history, hydraulic computations of spillway capacity and approximate hydrologic judgements.

c. Validity - A comparison of record data and visual observations reveals no observable significant discrepancies in the record data.

SECTION 3: VISUAL INSPECTION

3.1 FINDINGS

a. General - The condition of the project is fair based upon our visual inspection on May 12, 1980. The inspection revealed several areas requiring maintenance and monitoring. At the time of the inspection, the pond level was at elevation 311.0, i.e. 1.0 ft. below the top of the dam with a small amount of water flowing over the masonry spillway.

b. Dam

Top of Dam - The masonry coping contains cracks and deterioration within the mortar joints especially to the left side of the spillway. There is also vegetation growing from some of these cracks. The top of the earth embankment portion of the dam is bare and shows evidence of erosion (photos 1 and 2).

Upstream Slope - The upstream earthfill of the original dam section was below the water surface level therefore it could not be evaluated. The upstream slope of the embankment portion of the dam is irregular and badly eroded (Photo 2). Riprap had been removed or displaced from the embankment.

Downstream Slope - To the left of the spillway the slope is overgrown with large trees, brush and tall grass including numerous animal burrows (Photo 5). At the toe of the slope there is a seep of 5 gpm and a large wet area. The water from this seep was clear and flows toward the spillway channel. To the right of the spillway the slope is primarily covered by tall grass although some trees, tree stumps and brush exist near the spillway and channel area (photo 1). Animal burrows are evident in this area also. Extensive erosion has occurred behind the right masonry wingwall forming a large gully several feet deep. There is a large wet area at the toe to the right of the spillway from which a small stream develops, flowing at a rate of 4-6 gpm toward the spillway channel.

Spillway - The masonry spillway crest is in fair condition although there are some cracks and seepage through the masonry joints (photo 5). The approach channel is clear and free of obstructions. The training walls adjacent to the spillway crest show signs of slight erosion. Grasses and vines are growing from many of the joints in the masonry. Mortar is also missing from many of the joints (Photo 5). Seepage was observed from the joints of both training walls with flows averaging less than 1 gpm. The downstream face of the spillway is in fair condition although the masonry is a little eroded (Photo 4). The discharge channel is filled with debris and overgrown with trees and brush (Photos 4, 5 and 6).

c. Appurtenant Structure - The exterior of the brick gatehouse is in fair condition. In several areas, the concrete at the base of the brickwork, is deteriorated and the steel sheeting covering the vertical sides of the concrete base is pulled away or missing from the concrete. The wood decking, of the steel framed foot bridge is missing which makes entry to the gatehouse difficult. The wood floor inside the gatehouse is badly deteriorated. The handwheel of one of the valves has been removed from the pedestal.

d. Reservoir Area - The area surrounding the pond is generally wooded and undeveloped. There are steep wooded hills to the east and northwest and a golf course to the west of the dam.

e. Downstream Channel - The downstream channel is the natural streambed of Harbor Brook. The channel was very overgrown with large trees, brush, uprooted trees, and assorted grasses. It is difficult to define the actual channel.

3.2 EVALUATION

Based upon the visual inspection, the project is assessed as being in fair condition. The following features which could influence the future condition and/or stability of the project were identified.

1. Significant seepage through the masonry has and will continue leaching the cement mortar joints thus weakening the masonry and decreasing stability. Freezing and thawing of this seepage could result in displacement of the stonework and/or possible failure of the masonry.
2. Vegetation growing through the masonry joints could lead to displacement and/or possible failure of the masonry.
3. Cracks between the newer concrete and the upstream face of the original masonry (See Sheet B-1), allow water to flow through the masonry section thus possibly leading to adverse seepage through the dam.
4. The lack of riprap or other suitable protective cover on the top and upstream slope of the embankment portion of the dam will permit further erosion which may possibly result in failure of the structure.
5. Trees, brush and burrowing animals could promote piping and/or seepage by creating flow paths, either along root systems or through holes, in the embankment. Trees, if uprooted may produce depressions which may be critical to the stability of the dam.

6. Seepage and wet areas at the toe of the downstream embankment could increase and lead to instability if not properly monitored.
7. The wood decking is missing from the footbridge leading to the gatehouse, making it difficult as well as dangerous to get into the gatehouse.

SECTION 4: OPERATIONAL AND MAINTENANCE PROCEDURES

4.1 OPERATIONAL PROCEDURES

a. General - No formal program of operation is in effect. It was reported that the low-level outlet was opened in the summer of 1979 to provide water to a public swimming area downstream.

b. Description of any Warning System in Effect - No formal warning system is in effect.

4.2 MAINTENANCE PROCEDURES

a. General - There is no formal program of maintenance or inspection at the dam.

b. Operating Facilities - No formal program for maintenance of operating facilities is in effect.

4.3 EVALUATION

Operation and maintenance procedures are not performed. A formal program of operation and maintenance procedures should be implemented, including documentation to provide complete records for future reference. Also, an emergency action plan as well as a formal downstream warning system should be developed and implemented within the time frame indicated in Section 7.1c. Remedial operation and maintenance recommendations are presented in Section 7.3.

SECTION 5: EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES

5.1 GENERAL

The Bradley Hubbard Reservoir Dam drainage area is 0.59 square miles of wooded rolling to mountainous terrain. An ungated conduit upstream, diverts water to the reservoir and substantially increases the drainage area (See Sheet D-1).

The dam is basically a low surcharge storage - high spillage type project. The available storage reduces the outflow from a Probable Maximum Flood (PMF) from 1500 cubic feet per second (cfs) to 1325 cfs and the $\frac{1}{2}$ PMF outflow from 750 cfs to 620 cfs.

5.2 DESIGN DATA

No computations could be found for the original design of the dam or the subsequent raising.

5.3 EXPERIENCE DATA

The maximum discharge at this dam site is unknown and no information was found to indicate that there have been any problems (including overtopping) arising at the dam.

5.4 TEST FLOOD ANALYSIS

Based upon the U.S. Army Corps of Engineers "Preliminary Guidance for Estimating Maximum Probable Discharges" dated March, 1978; the watershed classification (rolling to mountainous) and the watershed area of 0.59 square miles, a PMF of 1500 cfs or 2550 cfs per square mile is estimated at the damsite. In accordance with the size (small) and hazard (high) classification, the range of test floods to be considered is from the $\frac{1}{2}$ PMF to the PMF. Based on the hazard potential associated with a breach of the dam, the test flood for Bradley Hubbard Reservoir Dam is selected as equivalent to the PMF. The pond level at the start of the test flood is considered to be at elevation 311.0, which is at the spillway crest. Peak inflow to the reservoir at the test flood is 1500 cfs; peak outflow is 1325 cfs with the dam overtopped by 0.9 feet. Based on hydraulics computations, the spillway capacity to the top of the dam is 223 cfs which is equivalent to 17% of the routed test flood outflow (Appendix D-6).

5.5 DAM FAILURE ANALYSIS

Utilizing the Corps of Engineers April 1978 "Rule of Thumb Guidance for Estimating Downstream Dam Failure Hydrographs", the peak failure outflow due to a breach of the dam is estimated to be 11,700 CFS with an estimated flood depth of 7 Ft. immediately downstream of the dam. The flood routing was performed for peak failure outflow with pool at top of dam. The prefailure flow in the brook is estimated to be 223 CFS and flood stages are estimated to increase by 4.3 Ft. and 7.9 Ft. at the initial and second impact areas respectively.

The estimated peak flow rates and peak flood depths at four sections downstream of the dam resulting from a dam failure are:

| <u>D/S Section</u> (Ft. From Dam) | <u>Flow</u> (CFS) | <u>Flood Depth</u> (Ft) | <u>Velocity</u> (FPS) |
|--------------------------------------|----------------------|----------------------------|--------------------------|
| At Dam | 11,700 | 7 | - |
| 1350 | 10,100 | 9.6 | 11 |
| 1950 | 9,400 | 6.6 | 11 |
| 2450 | 8,500 | 4.5 | 6 |
| 3800 | 6,000 | 11 | 5 |

As discussed in Appendix D (D-23 & 24), a flood of this magnitude would inundate a significant portion of George Hunter Golf course and flood at least two houses on Westfield Road. The flood depth in the golf course, considered as initial impact area, would vary from 6.6 ft. to 11 ft. in the vicinity of the existing channel. At the second impact area in the vicinity of Westfield Road, the house located north of the road has its first floor 7.6+ ft. above the channel bed, and would be inundated with 3.4+ ft. of flood water. Similarly, the house located south of the Westfield Road would be unundated with 2.2+ ft. of water, since its first floor elevation is 8.8+ ft. above the channel bed. In addition, it is expected that three culverts would be damaged and Westfield Road would be inundated with 2.5+ ft. of water at two locations.

Based upon the hydraulic and hydrologic analysis, the dam has a high hazard classification with a potential for loss of more than a few lives upon failure of the dam.

SECTION 6: EVALUATION OF STRUCTURAL STABILITY

6.1 VISUAL OBSERVATIONS

The dam is basically in two sections. The main section is the original stone masonry dam with earth fill added on the downstream side, and earth and rock fill added on the upstream side. The second section is the newer part of the dam added in 1912. This is an earth embankment with a concrete corewall, both of which abut the right end of the masonry core. This section was added to fill a low area resulting from raising the original dam 3.5 feet in 1912. The concrete corewall at the right end of the dam extends for 175 feet, through the earth embankment section and into the natural earth abutment. Another 30 foot section of concrete corewall was also added to the left end of the dam. The dam was raised by removing the cap stones, placing 3.5 feet of concrete on the top and replacing the cap stones (See Sheet B-1, Section B-B). The inclination of the rock fill on the upstream slope is 1.5 horizontal to 1 vertical and the inclination of the downstream slope is 2.0 horizontal to 1 vertical.

The visual inspection revealed a series of maintenance and repair related problems which, if not corrected, could compromise the stability of the dam. In summary, these would include: 1) cracking of the masonry joints and between the newer concrete and the original masonry, allowing seepage to occur through the masonry cap stones and through the spillway section, 2) seepage of approximately 5 gpm (clear water flowing) and a large wet area at the right and left ends of the toe of the dam, 3) animal burrows, erosion and fairly large trees on the downstream slopes, 4) erosion and lack of slope protection on the earth embankment section to the right end of the dam, 5) the poor condition of the gatehouse and operating facilities. See Section 7 for recommendations and remedial measures.

6.2 DESIGN AND CONSTRUCTION DATA

The drawings and data available and listed in Appendix B were not sufficient to perform an in depth stability analysis of the dam. No engineering assumptions, data or calculations could be found for the original design of the dam.

6.3 POST CONSTRUCTION CHANGES

Post construction changes of the project consisted of raising the crest of the dam 3.5 feet and the addition of 115 feet of embankment and a concrete corewall at each end of the dam to increase storage.

6.4 SEISMIC STABILITY

The project is in Seismic Zone 1 and according to the Recommended Guidelines, need not be evaluated for seismic stability.

SECTION 7: ASSESSMENT RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 DAM ASSESSMENT

a. Condition - Based upon the visual inspection of the site and past performance, the project appears to be in fair condition. However, there are areas which require maintenance, repair and monitoring.

Based upon the Army Corps of Engineers' "Preliminary Guidance for Estimating Maximum Probable Discharges" dated March, 1978, the watershed classification and hydraulic/hydrologic computations, peak inflow to the lake at the test flood is 1500 cubic feet per second (cfs); peak outflow is 1325 cfs with the dam overtopped 0.9 feet. Based upon our hydraulic computations, the spillway capacity to the top of dam is 223 cfs, which is equivalent to approximately 17% of the routed test flood outflow.

b. Adequacy of Information - The information available is such that an assessment of the condition and stability of the project must be based solely on visual inspection, past performance and sound engineering judgement.

c. Urgency - It is recommended that the measures presented in Section 7.2 and 7.3 be implemented within one year of the owner's receipt of this report.

7.2 RECOMMENDATIONS

It is recommended that further studies be made by a registered professional engineer qualified in dam design and inspection pertaining to the following items. Recommendations made by the engineer should be implemented by the owner.

1. A detailed inspection of the spillway and spillway channel when no water is flowing over the spillway to check for seepage through the masonry and erosion of the cobble apron at the base of the spillway.
2. Determination of the origin and significance of seepage and wet areas at the toe of the downstream embankment.
3. Removal of all trees, tree stumps, and brush from the embankments and the spillway channel. This should include removal of root systems, proper backfilling and regrading of eroded areas.
4. The upstream slope of the embankment portion of the dam should be regraded, riprap placed on the upstream slope and slope protection placed on the top of the embankment which will resist the frequent foot traffic.
5. A hydraulic/hydrologic analysis should be performed to more accurately determine the adequacy of the existing project discharge and the overtopping potential.

6. Sealing the cracks between the newer concrete section and the original masonry to prevent seepage through this area.

7.3 REMEDIAL MEASURES

a. Operation and Maintenance Procedures - The following measures should be undertaken by the owner within the length of time indicated in Section 7.1.c, and continued on a regular basis:

1. Round-the-clock surveillance should be provided during periods of heavy precipitation or high project discharge. A formal emergency preparedness plan should be devised so in the event of an emergency, evacuation may be implemented in a prompt and organized manner.
2. A formal program of operation and maintenance procedures should be instituted and fully documented to provide accurate records for future reference. The maintenance procedures should include a monthly inspection by the owner or owner representative.
3. A comprehensive program of inspection by a registered professional engineer qualified in dam inspection should be instituted on a biennial basis.
4. The vegetation should be removed from the masonry joints and all masonry repointed.
5. The gully on the downstream slope along the right spillway training wall, and any other visible slope erosion, should be backfilled with suitable material and proper slope protection placed.
6. Decking should be replaced on the footbridge to the gatehouse and fencing to protect against vandalism installed.
7. Flooring should be replaced in the gate house.
8. The gate house door should be repaired.
9. The gate valve mechanisms should be repaired, cleaned, lubricated, and painted.
10. The discharge channel should be cleared of trees, brush and logs, and the cobble apron repaired to prevent erosion at the base of the spillway during high spillway discharge.
11. Animal burrows should be evacuated, properly backfilled and slope protection placed.

7.4 ALTERNATIVES

This study has identified no practical alternatives to the above recommendations.

APPENDIX A
INSPECTION CHECKLIST

VISUAL INSPECTION CHECK LIST
PARTY ORGANIZATION

PROJECT Bradley Hubbard Reservoir Dam DATE: May 12, 1980

TIME: 9:30 - 10:30 Am

WEATHER: Cloudy 55°

W.S. ELEV. 311 U.S. _____ DN.S _____

| <u>PARTY:</u> | <u>INITIALS:</u> | <u>DISCIPLINE:</u> |
|-----------------------------|------------------|-------------------------------------|
| 1. <u>Peter Heynen</u> | <u>PH</u> | <u>Cohn, Geotechnical</u> |
| 2. <u>Miron Petrovsky</u> | <u>MP</u> | <u>Cohn, Geotechnical</u> |
| 3. <u>Jay Castello</u> | <u>JC</u> | <u>Cohn, Geotechnical</u> |
| 4. <u>Jeffrey Borne</u> | <u>JB</u> | <u>Cohn, Geotechnical</u> |
| 5. <u>Dr. Murali Atluru</u> | <u>MA</u> | <u>Diversified Tech, Hydraulics</u> |
| 6. _____ | _____ | _____ |

| <u>PROJECT FEATURE</u> | <u>INSPECTED BY</u> | <u>REMARKS</u> |
|----------------------------|---------------------------|----------------|
| 1. <u>Earth Embankment</u> | <u>PH, MP, JC, JB, MA</u> | <u>A-2</u> |
| 2. <u>Spillway</u> | <u>PH, MP, JC, JB, MA</u> | <u>A-3</u> |
| 3. <u>Gatehouse</u> | <u>PH, JC</u> | <u>A-4</u> |
| 4. _____ | _____ | _____ |
| 5. _____ | _____ | _____ |
| 6. _____ | _____ | _____ |
| 7. _____ | _____ | _____ |
| 8. _____ | _____ | _____ |
| 9. _____ | _____ | _____ |
| 10. _____ | _____ | _____ |
| 11. _____ | _____ | _____ |
| 12. _____ | _____ | _____ |

PERIODIC INSPECTION CHECK LIST

Page A-2

PROJECT Bramley Hubbard Reservoir Dam DATE 5-12-80

PROJECT FEATURE Earth Embankment BY LM, MC, JC, JB, MA

| AREA EVALUATED | CONDITION |
|---|---|
| <u>DAM EMBANKMENT</u> | |
| Crest Elevation | { 312.0 (masonry) 313.0 (earth) |
| Current Pool Elevation | 311.0 |
| Maximum Impoundment to Date | Not Known |
| Surface Cracks | Joint crack in masonry |
| Pavement Condition | N/A |
| Movement or Settlement of Crest | { None Observed |
| Lateral Movement | |
| Vertical Alignment | { Appears good |
| Horizontal Alignment | |
| Condition at Abutment and at Concrete Structures | Fair |
| Indications of Movement of Structural Items on Slopes | None observed |
| Trespassing on Slopes | Excessive trespassing on top of embankment section |
| Sloughing or Erosion of Slopes or Abutments | U/S slope embankment section |
| Rock Slope Protection-Riprap Failures | U/S slope embankment section - no riprap |
| Unusual Movement or Cracking at or Near Toes | None observed |
| Unusual Embankment or Downstream Seepage | Wet areas at U/S toe of dam to each side of spillway. |
| Piping or Boils | None observed |
| Foundation Drainage Features | N/A |
| Toe Drains | N/A |
| Instrumentation System | N/A |

A-2

PERIODIC INSPECTION CHECK LIST

Page A-3

PROJECT Bradley Hubbard Reservoir Dam

DATE 5-12-80

PROJECT FEATURE Spillway

BY PH, MP, JC, JB, MA

| AREA EVALUATED | CONDITION |
|--|---|
| <u>OUTLET WORKS-SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u> | |
| a) <u>Approach Channel</u> | |
| General Condition | Good |
| Loose Rock Overhanging Channel | No |
| Trees Overhanging Channel | No |
| Floor of Approach Channel | Stones on bottom - clear |
| b) <u>Weir and Training Walls</u> | |
| General Condition of Concrete | Fair |
| Rust or Staining | No |
| Spalling | little eroded, mortar leached from joints. |
| Any Visible Reinforcing | No |
| Any Seepage or Efflorescence | Seeps through joints (<1gpm) possible undermining at toe |
| Drain Holes | |
| c) <u>Discharge Channel</u> | |
| General Condition | Poor |
| Loose Rock Overhanging Channel | No |
| Trees Overhanging Channel | Area heavily wooded and overgrown. |
| Floor of Channel | Heavily wooded, brush, logs, |
| Other Obstructions | |

PERIODIC INSPECTION CHECK LIST

Page A-4

PROJECT Brookly Hubbard Reservoir Dam



DATE 5-12-80




PROJECT FEATURE Gatehouse

BY PH, MP, JC, JB, NA

| AREA EVALUATED | CONDITION |
|--|--|
| <u>OUTLET WORKS-CONTROL TOWER</u> | |
| a) <u>Concrete and Structural</u> | |
| General Condition | Poor |
| Condition of Joints | Cracking of concrete foundation and brick superstructure |
| Spalling | Some |
| Visible Reinforcing | None observed |
| Rusting or Staining of Concrete | |
| Any Seepage or Efflorescence | |
| Joint Alignment | N/A |
| Unusual Seepage or Leaks in Gate Chamber | None observed |
| Cracks | yes - brickwork and concrete foundation |
| Rusting or Corrosion of Steel | yes - steel sheeting around foundation |
| b) <u>Mechanical and Electrical</u> | |
| Air Vents | N/A |
| Float Wells | |
| Crane Hoist | |
| Elevator | |
| Hydraulic System | |
| Service Gates | |
| Emergency Gates | |
| Lightning Protection System | |
| Emergency Power System | |
| Wiring and Lighting System | |

APPENDIX B
ENGINEERING DATA AND CORRESPONDENCE





NOTES:

- 1 THIS DRAWING TRACED FROM A PLAN TITLED "DAM AT STORAGE RESERVOIR" PREPARED FOR THE BRADLEY & HUBBARD MFG CO. AND THE INTERNATIONAL SILVER CO. NO DATE OR INDICATION WHO PREPARED THE PLAN WAS AVAILABLE
- 2 ALL ELEVATIONS ARE NGVD BASED ON AN ASSUMED SPILLWAY CREST ELEVATION. THE WATER SURFACE ELEVATION OF 311.0 SHOWN ON THE 1972 MERIDEN USGS QUADRANGLE MAP WAS ASSUMED TO BE THE ELEVATION OF THE SPILLWAY CREST. ALL OTHER ELEVATIONS ARE REFERENCED TO THE SPILLWAY CREST ELEVATION.

| | | | |
|---|------------|--|--------------------------|
| CAMN ENGINEERS INC WALLINGFORD, CONNECTICUT ENGINEER | | U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS | |
| NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS PLAN, ELEVATION AND SECTION | | | |
| BRADLEY HUBBARD RESERVOIR DAM | | | |
| HARBOR BROOK | | MERIDEN, CONNECTICUT | |
| DRAWN BY | CHECKED BY | APPROVED BY | SCALE AS NOTED |
| 1/1 | 1/1 | 1/1 | DATE SEPT 1980 SHEET B-1 |

2

BRADLEY HUBBARD RESERVOIR

EXISTING PLANS

"International Silver Company and Bradley and Hubbard Mfg. Co.,
Dam at Storage Reservoir"

No date or signatures.

SUMMARY OF DATA AND CORRESPONDENCE

| <u>DATE</u> | <u>TO</u> | <u>FROM</u> | <u>SUBJECT</u> | <u>PAGE</u> |
|-------------------|---|---|---|-------------|
| Sept. 25 1912 | | | Contract and specification between owners, International Silver Co. and The Bradley and Hubbard Co., and contrac- tor, Leonardo Suzio, in reference to raising the dam | B-3 |
| June 11, 1963 | File | State Board for the Supervision of Dams | Inventory Data | B-12 |
| May 3, 1965 | John J. Mozzochi and Associates | William P. Sanders Water Resources Commission | Inspection Request | B-13 |
| June 14, 1965 | William P. Sanders Water Resources Commission | John J. Mozzochi and Associates | Results of Dam Inspection | B-14 |
| June 21, 1965 | BeElden A. Philbrook Soil Conservation | William P. Sanders | Cover letter for dam inspec- tion by John J. Mozzochi and Associates | B-15 |
| April 26, 1973 | Victor Galgowski Conn. Dept of Environ- mental Protection | Buck and Buck Engineers James A. Thompson | Visual dam inspection results | B-16 |
| May 10, 1973 | Mayor Abraham G. Grossman - Meriden, Ct. | Victor Galgowski | Inspection report and recom- mendation. | B-17 |
| May 15, 1973 | Dan W. Lufkin Conn. Dept. of Environ- mental Protection | Mayor Abraham G. Grossman | Request of detailed recommen- dations | B-18 |
| July 8, 1974 | Douglas Mcostle Conn. Dept. of Environ- mental Protection | Mayor John D. Quine - Meriden, Ct. | Request of detailed recommen- dations | B-19 |
| July 17, 1974 | Mayor John D. Quine | Victor Galgowski | Detailed recommendations | B-21 |

AND
THE BRADLEY & HUBBARD MFG. CO.

RAISING PRESENT DAM

MERIDEN, CONN.

THIS AGREEMENT made and concluded this 25th day of September 1912, by and between The International Silver Co., and The Bradley & Hubbard Mfg. Co., corporations organized under the Laws of the State of Connecticut, and having their place of business in the City of Meriden in said State, Party of the First Part, and Leonardo Suzio Contractor, Party of the Second Part,

WITNESSETH:

(A) That the said party of the second part has agreed and by these presents does agree with the said party of the first part, for the consideration hereinafter mentioned and contained, to furnish all necessary labor and tools, and to construct in a substantial and workmanlike manner, the additions to the present dam of the party of the first part in the Town of Meriden, in the manner, and under the conditions hereinafter specified; and has further agreed that the said party of the first part shall be, and is, hereby authorized to appoint its engineer, and such other person or persons as it may deem proper, to inspect materials furnished and the work done, and to see that the same correspond with the specifications hereinafter set forth, to wit:

(B)

SPECIFICATIONS

(1) WORK TO BE DONE.

B-3

The work contemplated and provided for in this

house about three feet and five inches; the construction of additional embankments on both sides of the present dam; and the construction of an earth dam with concrete core wall at each end of the present dam.

All materials shall be provided by the contractor, excepting that stone suitable for use in the work may be obtained on the property of the International Silver Co., and The Bradley & Hubbard Mfg. Co.

All work shall be done strictly in accordance with the plan on file in the office of The Bradley & Hubbard Mfg. Co.

(2) ADDITION TO THE PRESENT DAM.

The coping stones on the present dam and the two upper courses of stone on the spillway shall be removed and placed at convenient places on the embankment. All loose stone and mortar on top of the masonry wall shall be removed so as to give a good bond between the new concrete and masonry.

A concrete wall shall be built on top of this masonry of the size and dimensions shown on the plan. The concrete facing on the back of the dam shall be carried down into the water from one to two feet as directed by the engineer.

A 3/4" square steel rod 8 feet long bent as shown on the plans shall be placed in the concrete and spaced every two feet as shown on the plan.

The dam shall be divided in sections of about fifty feet or such length that all the concrete in the section can be placed in the same day. At the end of each section a vertical groove shaped as directed by the engineer, shall be made in the concrete to form an expansion joint. The end of each section shall be oiled, before the concrete in the next section is placed.

planed planks. Adjoining planks of the same mold shall be of the same thickness with the edges beveled, or tongues and grooved to make the joints water tight.

All molds shall be thoroughly cleaned of all cement before being used. Deformed, broken, or defective molds shall be repaired or removed from the work.

The molds shall be allowed to remain in place a sufficient length of time to allow the concrete to set; and they shall be constructed in such a manner that they can be readily removed without jarring or cracking the concrete.

Forms may be omitted for the vertical sections of the core walls provided that the excavation is made truly to the widths shown on the plan.

(11) CEMENT.

All cement used in the work shall be of the best quality of Portland cement of a brand that has an established reputation for uniformity and quality. It shall be dry and free from lumps; be ground so finely that ninety-two per cent will pass a sieve with ten thousand meshes to the square inch; and parts of neat cement one half inch in thickness and three inches in diameter with thin edges shall not crack in setting or when immersed in water maintained at a temperature of one hundred and seventy-five degrees Fahrenheit. The color shall remain uniform over the whole surface of the cement after becoming hard, and not show yellowish spots, whether the tests are set in air or in water.

Briquettes, molded of neat cement, shall have a tensile strength of at least one hundred and fifty pounds per square inch after twenty four hours immersion in water - the briquette to be placed in water immediately after being set - and at least five hundred pounds after one day in air and six days in water; 8-5 and shall show a gradually increasing strength after that time.

the wall shall be covered with a thick bed of mortar and the coping stones set thereon. If so directed by the engineer, the paving in the cobble apron next to the spillway shall be removed for a width of about three feet, and a section of concrete about two feet deep be thoroughly rammed into the space.

(3) RAISING THE GATE HOUSE.

The present gate house and bridge shall be raised approximately three feet five inches as shown on the plan. The gate house shall be jacked up with timbers, and the foundations carried up with ^{stone} ~~brick~~ to the under side of the sand stone water table. The ladder in the gate wall and the gate stems shall be lengthened to fit the new floor level.

(4) EXCAVATION.

The earth on the site of the core walls shall be excavated down to rock, and a trench shall be excavated in the rock, if necessary, to a sufficient depth to secure a good foundation for the concrete. The width of the excavation shall be the same width as the core wall.

On the site of the embankments for the core wall, all loam, stumps, roots, and other vegetable matter shall be grubbed out and removed from the entire area to be covered by the new work. The loam shall be piled at one side of the excavation and be used for surfacing the embankments.

The loam on the embankments in front of the present dam shall be removed before building the additional embankments.

The excavation for the concrete on back of the present dam shall be carried down into the selected material, and from one to two feet into the water, as directed by the engineer.

Wherever rock is encountered in the excavations it shall be stripped of earth and the engineer notified that he may cross-section the same.

Special care shall be taken in preparing the foundations for the core wall to shatter the surrounding rock as little as possible. All loose rock must be removed, ~~and~~ without blasting.

Only ledge rock and boulders measuring more than one half of a cubic yard in volume shall be measured as rock.

(6) EMBANKMENTS.

After the loam and other soft material has been removed from the site of the embankments the earth beneath shall be loosened by plowing or harrowing to secure a bond between the natural soil and the new material.

Only selected material which will "pack" when moistened and tamped shall be used in the embankment on the water side of the core wall. At the back of the present dam the rip rap shall be removed as low as the water in the reservoir will permit, and be replaced with selected material.

The down stream side of the core wall embankment, and the embankment in front of the present dam may be made of gravel or other material which will form a solid bank. No stumps or other vegetable substances, and no stones which are too large to be thoroughly bedded by the tampers shall be used.

The material for the embankments shall be taken from the excavation for the core walls or from the reservoir basin below the flow line. It shall be deposited in horizontal layers not exceeding six inches in depth, be sprinkled with water, and thoroughly tamped with heavy iron tampers. The amount of water used, and the extent to which the material shall be tamped shall be regulated by the engineer

slope of one on two. The up stream or water face of the embankment shall be covered with rip rap to a level two feet above the level of the top of the spillway. The remainder of the embankments shall be covered with a layer of black loam to a depth of at least six inches and be well seeded with grass of the variety determined by the engineer.

The rip rap shall be composed of sound and durable stones and be of such size and shape as to form a facing at least one foot in depth. The stones shall be set by hand close together, the interstices between the larger stones being chinked up with spalls and small stones to make a smooth and compact surface. After the rip rap is laid sand or gravel shall be spread over the surface and be broomed into the joints until all spaces between the stones are solidly filled.

(7) ROCK FILL.

The rip rap on the upstream slope of the present dam shall be covered to a depth of about two feet with broken rock of a size which can be handled by one man. The face of this rock fill shall be graded on a slope of one on one and one half.

(8) CORE WALL.

A concrete core wall shall be built at both ends of the present dam, and be extended into the natural bank at each side as directed by the engineer. It shall be founded on solid rock, and be carried up within one foot of the top of the embankment.

(9) CONCRETE.

All concrete used in the work shall be composed of one part of cement, two and one half parts of fine, and four and one half parts of coarse aggregate.

the surface shall be washed with a thin grout of cement and sand and be floated with soft wooden floats until the surface is smooth and hard.

The concrete and mortar shall be made in concrete mixing machines of approved form. The ingredients for a "batch" shall be assembled in suitable measuring boxes before being placed in the mixer. The cement and sand shall first be mixed to a thin mortar, the stone afterwards added, and the mixing continued until a homogeneous mixture is obtained.

The concrete shall be mixed "wet", but the exact amount of water shall be determined by the engineer. It shall be deposited in place immediately after being mixed, and be thoroughly compacted by tamping, and by spading along the sides of the forms.

No work in concrete shall be done when the temperature is below freezing.

The surface of the rock, the top of the present dam, and concrete which has set shall be covered with a thin layer of mortar before the placing of any concrete thereon. The mortar shall be composed of one part of cement and two and one half parts of sand.

Where new masonry is joined to old, the surfaces of the old concrete shall be cleaned of all laitance, and soft or loose cement, by scrubbing with wire brushes, and be thoroughly washed.

(10) FORMS.

The forms or molds for the different parts of the work shall be built of the exact shape of the structures which they are to form; and be of sufficient strength and rigidity to permit of the concrete being thoroughly tamped and compacted without springing or warping them from that shape. B-9

cient amount of cement on hand to permit of its being tested before being used.

The cement shall be kept stored in a tight shed so constructed that the cement will be protected from the weather and from dampness from the ground.

A barrel of cement shall be reckoned as three hundred and eighty pounds net weight.

(12) AGGREGATES.

The fine aggregate shall be clean, sharp pit sand, free from clay or loam, or fine stone dust such as will pass a sieve with one quarter of an inch mesh.

The coarse aggregate shall be broken stone such as will pass a screen with two inch round holes and be rejected by a sieve with one quarter of an inch mesh. Only hard, durable stone will be accepted.

(13) BRICK.

The ^{stone} ~~brick~~ used in the gate house foundation shall be regular and uniform in shape and size, with full sharp corners, and be hard burned entirely through. They shall be thoroughly wet with water before being laid, and have full cement joints, at bed, sides, and ends, which shall be made at one operation and not by working the mortar in after the brick is laid.

The joints shall be properly struck on the face of the work.

(14) STEEL.

The steel rods used in the work shall be of the size shown on the plan. They shall be placed in the work in such a manner as to be thoroughly covered with concrete; and shall be truly bent to the form directed by the engineer.

(15) PROTECTION OF WATERSHED.

All buildings for housing the men or animals employed on the work shall be built on land entirely off the watershed of the present reservoir. They shall be kept at

AND

THE BRADLEY & HUBBARD MFG. CO.

RAISING PRESENT DAM

MERIDEN, CONN.

ESTIMATE OF QUANTITIES.

| | | |
|---------------------------------------|---------------|---------|
| Earth Excavation - - - - - | 500 cu. yds. | 750.00 |
| Rock Excavation - - - - - | 10 cu. yds. | 25.00 |
| Rolled Earth Embankment - - - - - | 1200 cu. yds. | 1200.00 |
| Concrete - - - - - | 700 cu. yds. | 4935.00 |
| Rock Filling - - - - - | 250 cu. yds. | 1175.00 |
| Rip Rap - - - - - | 75 sq. yds. | 1125.00 |
| Steel - - - - - | 3000 lbs. | 700.00 |
| Coping stones to be moved - - - - - | 425 lin. ft. | 403.75 |
| Brick for gate house foundation - - - | 7000 | 550.00 |

7757.00

The above quantities are to be considered only as approximate. The International Silver Co., and The Bradley & Hubbard Mfg. Co. reserve the right of increasing or diminishing the same as may be deemed necessary by the engineer.

E

No. ME 3

WATER RESOURCES COMMISSION
SUPERVISION OF DAMS
INVENTORY DATA

Inventoried
By WPS

Date 11 JUNE 1963

CT-132 1

Long 72-45.7

Lat 41-53.5

Name of Dam or Pond BRADLEY HUBBARD RESERVOIR

Code No. QU 234 HR 5.6

Nearest Street Location WESTFIELD ROAD

Town MERIDEN

U.S.G.S. Quad. MERIDEN

Name of Stream HARBOR BROOK

Owner CONNECTICUT LIGHT AND POWER CO. CITY OF MERIDEN

Address BERLIN

City Hall
Meriden

02
7/73

Pond Used For WATER SUPPLY (?) DA 0.5984

Dimensions of Pond: Width 500 FEET Length 3000 FEET Area 34.0 ACRES

Total Length of Dam 280 FEET Length of Spillway 40 FEET

Location of Spillway EAST END OF DAM

Height of Pond Above Stream Bed 15 FEET

Height of Embankment Above Spillway 3 FEET

Type of Spillway Construction MASONRY

Type of Dike Construction MASONRY

Downstream Conditions FIELDS ROADS

Summary of File Data

Remarks

Would Failure Cause Damage? YES B=12 Class B

May 3, 1965

John J. Mozzochi and Associates
217 Hebron Avenue
Glastonbury, Connecticut

Gentlemen:

Under the terms of your contract as consultant to this Commission, will you please inspect and report on Bradley Hubbard Reservoir in Meriden. There is a proposed flood control project at Baldwin Pond immediately downstream and for this reason we would like to know the present condition of Bradley Hubbard Reservoir.

The Bradley Hubbard Reservoir is just east of Route 15 on the east side of the Meriden Quadrangle.

Very truly yours,

William P. Sander
Engineer - Geologist

WPS:jc

JOHN J. MOZZOCHI AND ASSOCIATES
CIVIL ENGINEERS

JOHN J. MOZZOCHI

ASSOCIATES

OWEN J. WHITE
JOHN LUCHS, JR.
ECTOR L. GIOVANNINI

June 14, 1965

WATER RESOURCES
COMMISSION
RECEIVED

GLASTONBURY, CONN.
217 HEBRON AVENUE
PHONE 622-8401

PROVIDENCE 2, R. I.
198 DYER STREET
PHONE GASPER 1-0420

REPLY To: Glastonbury


William P. Sander-Engineer - Geologist
Water Resources Commission
State Office Building
Hartford 15, Connecticut

Re: Our File 57-73-68
Bradley Hubbard Reservoir
Meriden, Connecticut

Dear Mr. Sander:

In accordance with your instructions of May 3, 1965, I made an inspection of the referenced dam on June 10th and found that it is in substantially good condition. There is some minor leakage noted around the spillway which appears to be due to the need of pointing of joints below the large sandstone capstones. This is a matter of routine maintenance only and should not be construed to be of any immediate importance.

The dam itself is about 460' overall consisting of an earthen dike about 100' long on the west end, a center masonry spillway section about 80' in length and 18' high with about a 12 inch freeboard, and two masonry capped abutment sections having concrete cores and earthen slopes, about 180' long on the west of the spillway and about 100' long on the east side, being apparently constructed to act as supplementary additional spillways, with about 12" freeboard to the earth dike on the west end.



In my opinion, this dam is in perfectly safe condition and should not be a cause for concern to any structure immediately downstream.

Very truly yours,

John J. Mozzochi
John J. Mozzochi and Associates
Civil Engineers

JJM:hk

B-14

June 21, 1965

Mr. BeElden A. Philbrook
U. S. Department of Agriculture
Soil Conservation Service
Old Bookstore Building
Route 195
Storrs, Connecticut

Dear Mr. Philbrook:

Enclosed is a copy of a report from one of our consulting engineers on the present condition of the Bradley Hubbard Reservoir in Meriden. Mr. John Curry of this office asked me to send you this copy in connection with the flood control project downstream.

We trust that this information will be of value to you.

Very truly yours,

William P. Sander
Engineer - Geologist

WPS:js

enclosure

BUCK & BUCK
E N G I N E E R S

98 WADSWORTH STREET, HARTFORD, CONNECTICUT 06106

JAMES A. THOMPSON
ROBINSON W. BUCK
LAWRENCE F. BUCK

HENRY WOLCOTT BUCK
1931-1968
ROBINSON D. BUCK
1935-1968

COMM. 5713-76

April 26, 1973

Mr. Victor Galgowski,
Department of Environmental Protection,
Water Resources Division,
State Office Building,
Hartford, Connecticut 06106

Re: Bradley Hubbard Reservoir Dam
Meriden

Dear Vic:

We inspected the subject dam on April 12th, and found the cap stones in need of pointing. Leakage through the dam, under the cap stones is beginning to erode the downstream earthen face of the dam. We also noted woodchuck holes on the downstream slope. These holes should be plugged and the woodchucks eradicated.

The repointing of the cap stones should be done from the upstream side and it may have to include complete rebedding of some stones. All of this work may be considered ordinary maintenance that does not require a permit. I suggest that the owner notify your office when the work is being done so that you can make a follow-up inspection.

Sincerely,

BUCK & BUCK


James A. Thompson

JAT:fb

**WATER & RELATED
RESOURCES
RECEIVED**

MAY 3 1973

ANSWERED _____
REFERRED _____
FILED _____

B-16

10 May 1973

The Honorable Abraham G. Grossman
City Hall
Meriden, Connecticut 06450

Re: Bradley Hubbard Reservoir Dam
Meriden

Dear Mayor Grossman:

A recent inspection, by one of our consultants, has indicated the need for some maintenance work on the subject dam.

In general, the cap stones need to be repointed from the upstream side and this may include complete rebedding of some stones. The present condition of the cap stones is allowing leakage through the dam and subsequent erosion of the downstream earthen face of the dam. Also noted on the downstream slope are woodchuck holes which should be plugged and the woodchucks eradicated.

The work involved would most likely be considered ordinary maintenance and would not require the issuance of a permit by this office.

Will you please notify this office within two weeks as to your intentions in regard to this matter.

Very truly yours,

Victor F. Galgowski
Supt. of Dam Maintenance
Water & Related Resources

VFG:ljg

B-17



OFFICE OF THE MAYOR
MERIDEN, CONNECTICUT 06450

ABRAHAM G. GROSSMAN
MAYOR

RECEIVED

MAY 18 1973

DEPT. OF ENVIRONMENTAL PROTECTION
PRESERVATION & CONSERVATION DIV.

May 15, 1973

**WATER & RELATED
RESOURCES
RECEIVED**

MAY 21 1973

Dan W. Lufkin, Commissioner
Department of Environmental Protection
State Office Building
Hartford, Connecticut 06115

ANSWERED _____
REFERRED _____
FILED _____

Re: Bradley Hubbard Reservoir Dam - Meriden

Dear Commissioner Lufkin:

I am in receipt of your transmittal of May 10, 1973 in which you indicate that a recent inspection was made by one of your consultants relative to the subject matter.

Could you please furnish this office with the name of the consultant and his complete report so that we may make a determination as to the condition of the Dam, the extent of his recommendations relative to the work to be accomplished and any recommendations you have for carrying out the work.

The generalities which you point out in your communication cannot form a basis for the course of action that must be taken by the City of Meriden.

Upon receipt of the information requested herein, I will transmit such information to the Board of Public Works for their considerations.

Thank you for your cooperation.

Very truly yours,

Abraham G. Grossman
Mayor

FSN:cag

B-18


cc: Public Works Dept.



OFFICE OF THE MAYOR
MERIDEN, CONNECTICUT 06450

JOHN D. QUINE
MAYOR

July 8, 1974



Douglas M. Costle, Commissioner
Department of Environmental Protection
State Office Building
Hartford, Connecticut 06115

Re: Crescent Lake (Bradley and Hubbard Reservoir
Dam) - Meriden

Dear Commissioner:

Please be advised that a transmittal dated May 15, 1973 from former Mayor Abraham G. Grossman to former Commissioner Lufkin has gone unanswered.

The generalities pointed out in the letter cannot form an organized basis for a course of action. Would you please furnish the City of Meriden with the following:

1. The name of the consultant who inspected the dam.
2. A complete report of the consultant's inspection and recommendations.
3. Please advise me if you are prepared to pay the cost for an engineering inspection of the dam.
4. Please advise me if you are prepared to pay for the cost of the design services.
5. Please advise me if you have any programs by which financial and technical assistance is available to make the inspection prepare the necessary engineering documents for repair and to pay for the repairs as necessary.

It is noted in your transmittal of May 10, 1973, that the woodchuck holes should be plugged and the woodchucks eradicated


-2-

Please send me the proper procedure for plugging the wood-chuck holes and eradicating the woodchucks.

Upon receipt of the information requested herein, I shall transmit such information to the Board of Public Works for their action.

Thank you for your cooperation.

Very truly yours

A handwritten signature in dark ink, appearing to read "John D. Quine", is written over the typed name and title.

John D. Quine
Mayor

JDQ:cg:N

cc: Victor Galgowski
Supt. of Dam Maintenance



STATE OF CONNECTICUT

DEPARTMENT OF ENVIRONMENTAL PROTECTION
STATE OFFICE BUILDING • HARTFORD, CONNECTICUT 06115

copy

17 July 1974

Honorable John D. Quine
City Hall
Meriden, CT 06450

Re: Bradley and Hubbard Reservoirs
Meriden

Dear Mayor Quine:

Commissioner Costle has directed me to reply to your letter of July 8, 1974 pertaining to the subject dam.

I am enclosing a copy of our consultant's inspection report; also information on woodchuck eradication.

As indicated in my letter of May 10, 1973 to the former mayor, the required work at this site is of a maintenance nature and would not require a construction permit from our office. From the standpoint of a sound dam maintenance program the repairs are warranted.

Responsibility for maintaining dams rests with the owners of such structures. The Department of Environmental Protection does not have available funds to provide financial assistance for this type of work.

Woodchuck infestation of earthen dikes or dams is a matter that can not be treated lightly. Burrows dug into these structures can weaken the structure and lead to failure. Of the enclosed suggested methods for woodchuck eradication, we find gas bombs to be the most effective. I am sure members of your Public Works Department are familiar with this technique. The Wildlife Unit of our department will provide additional information and suggestions if needed. The person to contact is Dennis DeCarli at 566-2841.

After woodchucks have been eliminated from a dam, it is advisable to excavate around the burrows and refill the void with suitable well tamped material. An erosion-preventive cover should be provided for the disturbed surface. An alternate procedure is to fill the burrow with a concrete slurry. The important factor is to seal channels through which water could seep and eventually lead to erosion and failure of the dam.

I sincerely hope that the foregoing information will enable you to take the action necessary to place this structure in satisfactory condition. If you have further questions, please do not hesitate to call.

Very truly yours,

Victor F. Galgowski
Supt. of Dam Maintenance
Water & Related Resources
Telephone no. 566-7280

VFG:ljg

B-21

Enclosure

APPENDIX C
DETAIL PHOTOGRAPHS




PHOTO NUMBER AND
 DIRECTION
 ↓

PHOTO LOCATION PLAN
 BRALEY HUBBARD
 RESERVOIR DAM

SHEET C-1



Photo 1 - Top of dam from right abutment. Note lack of protective cover on dike section in foreground (5/12/80)



Photo 2 - Upstream embankment of dike section (5/12/80)

US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS

CAHN ENGINEERS INC.
WALLINGFORD, CONN.
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Bradley Hubbard Res. Dam
Harbor Brook
Meriden, CT

CE # 27 785 KE

DATE Aug. '80 PAGE C-1



Photo 3 - Upstream side of masonry coping and gatehouse structure (5/12/80)



Photo 4 - Stepped masonry spillway wall. Note vegetation in spillway channel and grass growing from masonry joints. (5/12/80)

US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS

CAHN ENGINEERS INC.
WALLINGFORD, CONN
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Bradley Hubbard Res. Dam
Harbor Brook
Meriden, CT

CE# 27 785 KE

DATE Aug '80 PAGE C-2



Photo 5 - Masonry spillway crest and left end of dam
(5/12/80)



Photo 6 - View of spillway discharge channel from spillway
crest (5/12/80)


US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS

CAHN ENGINEERS INC.
WALLINGFORD, CONN
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Bradley Hubbard Res. Dam
Harbor Brook
Meriden, CT
CE# 27 785 KE
DATE Aug. '80 PAGE C-3

APPENDIX D
HYDRAULICS/HYDROLOGIC COMPUTATIONS



PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-16 SHEET 1 OF 25
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/12/80
BRADLEY HUBBARD RES. DAM CHECKED BY EB DATE 7/14/80

PERFORMANCE AT PEAK FLOOD CONDITIONS

PROBABLE MAXIMUM FLOOD (PMF) DETERMINATION -

DRAINAGE AREA - 0.59 SQ. MI. FROM CONN. STATE DEP BULLETIN
NO. 1, 1972 (GAZETTEER OF NATURAL
DRAINAGE AREAS, P-48)

WATERSHED CLASSIFICATION - "ROLLING" TO "MOUNTAINOUS"
BASED ON USGS MAP AND SITE VISIT.

PMF PEAK INFLOW -

PER CORPS OF ENGINEERS GUIDANCE NOT TO EXCEED
2500 CFS/SQ. MI. FOR D.A. \leq 2 SQ. MI., THE PEAK FLOW RATE
SELECTED = 2500 CFS/SQ. MI. FOR ABOVE CONDITIONS.

\therefore PMF PEAK INFLOW = $2500 \times 0.59 \approx 1500$ CFS

SIZE CLASSIFICATION -

FOR THE PURPOSE OF DETERMINING PROJECT SIZE, THE
MAXIMUM STORAGE ELEVATION IS CONSIDERED EQUAL TO
THE TOP OF DAM

TOP OF DAM = EL. 312.0 *

HEIGHT OF DAM = 16.5 FT (FROM EXISTING DRAINAGE)

* THE W.S. ELEVATION 311' MSL ON THE MERIDEN ST. QUADRANGLE
SHEET (REV. 1972) IS ASSUMED TO BE THE SPILLWAY CREST
ELEVATION ON NATIONAL GEODETIC VERTICAL DATUM (NGVD).
ALL OTHER ELEVATIONS ARE REFERENCED TO THIS ASSUMED
ELEVATION.

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-16 SHEET 2 OF 25
NEW ENGLAND DIVISION COMPUTED BY MAF DATE 7/12/80
BRADLEY HUBBARD RES. DAM CHECKED BY Eb DATE 7/14/80

PLANIMETERING FROM USGS MAP FOR RESERVOIR SURFACE AREA

AT EL. 311 (SPILLWAY CREST) = 35 ACRES

AT EL. 320 = 44 ACRES

AT EL. 330 = 56 ACRES

A STAGE-RESERVOIR AREA CURVE IS PLOTTED (SHEET 3)
FROM THIS CURVE, RESERVOIR AREA AT TOP OF DAM \approx 35.8 ACRES
AVERAGE RESERVOIR AREA BETWEEN SPILLWAY CREST
AND TOP OF DAM \approx 35.5 AC
STORAGE BETWEEN SPILLWAY CREST & TOP OF DAM

$$= 1 \times 35.5 = 35.5 \text{ AC.FT.}$$

ESTIMATED STORAGE BELOW SPILLWAY CREST = $\frac{1}{3} b h$

$$= \frac{1}{3} \times 35 \times 15.5 = 180 \text{ AC.FT.}$$

$$(b = 35 \text{ AC.FT.}, h = \text{EL. 311} - \text{EL. 295.5} = 15.5')$$


$$\therefore \text{MAXIMUM IMPOUNDMENT TO TOP OF DAM} = 35.5 + 180 \approx 216 \text{ AC.FT.}$$

A STAGE-STORAGE CURVE IS PLOTTED ON SHEET 3.
THUS, ACCORDING TO CORPS OF ENGINEERS GUIDELINES
TABLE 1, THE BRADLEY HUBBARD RESERVOIR DAM IS
CLASSIFIED SMALL BASED UPON THE STORAGE CAPACITY
OF 216 AC.FT. (< 1000 AND ≥ 50) AND HEIGHT OF THE
DAM IS ONLY 19.5'.

SHEET 3 OF 25

MA 7/12/80
CB 7/14/80

BRADLEY HUBBARD RESERVOIR



STORAGE ABOVE SPILLWAY CREST - AC FT

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-16 SHEET 4 OF 25
NEW ENGLAND DIVISION COMPUTED BY MW DATE 7/12/80
BRADLEY HUBBARD RES. DAM CHECKED BY EH DATE 7/14/80

HAZARD POTENTIAL - HIGH HAZARD POTENTIAL
 DAM BASED ON DAM BREACH ANALYSIS AND RELATIVE
 LOCATIONS OF GOLF COURSE, HOUSES AND OTHER STRUCTURES.
 A DETAILED DISCUSSION OF HAZARD POTENTIAL IS
 INCLUDED AT THE END OF BREACH ANALYSIS SECTION OF
 APPENDIX -D.

SELECTION OF TEST FLOOD -
 FOR THE SMALL SIZE AND HIGH HAZARD POTENTIAL
 CLASSIFICATION, TABLE 3 OF CORPS OF ENGINEERS RECOMMENDED
 GUIDELINES, THE TEST FLOOD COULD BE IN THE $\frac{1}{2}$ PMF
 TO PMF RANGE. BASED ON THE INVOLVED RISK POTENTIAL
 DOWNSTREAM OF THE DAM, A TEST FLOOD = PMF IS
 SELECTED (HIGH END OF THE RANGE)

TEST FLOOD PEAK INFLOW = 1300 CFS

PMF WOULD RESULT FROM 19" RUN-OFF FROM 0.59 DM.
 OF D.A.

1. TOTAL STORM VOLUME = $\frac{19}{12} \times 0.59 \times 640 \approx 600 \text{ AC.FT.}$
 THUS, MAXIMUM STORAGE (BETWEEN SPILLWAY CREST
 AND TOP OF DAM) OF 35.5 AC.FT. IS ONLY 6% OF
 THIS STORM VOLUME.

NOTE: SURCHARGE STORAGE ROUTING IS PERFORMED
 FOR $\frac{1}{2}$ PMF PEAK INFLOW ALSO

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION

PROJECT NO. 80-10-16

SHEET 5 OF 25

NEW ENGLAND DIVISION


COMPUTED BY mt

DATE 7/12/80

BRADLEY HUBBARD RES. DAM

CHECKED BY SL

DATE 7/14/80



POTENTIAL OVERFLOW PROFILE

(BASED ON EXISTING INFORMATION & CE FIELD OBSERVATIONS)

SPILLWAY

$$Q_1 = C L H^{3/2}$$

$$= 223 H^{3/2}$$

C = 3.1 FOR BROAD CRESTED LAIR, BASED ON THE DIMENSIONS OF THE STRUCTURE, U/S & D/S SLOPES PER FIG. 7. OF USGS BOOK 3, CHAPTER A-5, "MEASUREMENT OF PEAK DISCHARGE AT DAMS BY INDIRECT METHODS"

$$CR. EL. = 311 \quad L = 72'$$

DAM

$$Q_2 = C L H^{3/2}$$

$$= 737 H^{3/2}$$

C = 2.7 FOR SPILLWAY CRESTED LAIR.
CR. EL. = 312, L = 183' + 90' = 273'


DIKE

$$Q_3 = Q_3' + Q_3''$$

$$Q_3' = \frac{2}{3} C L \left(\frac{h_b^{5/2}}{h_b - h_a} \right) *$$

C = 2.9 ASSUMED L = 45' (APPROXIMATE)

EL. = 312, h_a = 0 UP TO EL. 313



*NOTE: USGS RECOMMENDED FORMULA FOR MORE PRECISE DISCHARGE OVER INCLINED DAM/EMBANKMENT CREST

(REF: MEASUREMENT OF PEAK DISCHARGES AT DAMS BY INDIRECT METHODS, USGS BOOK 3, CHAPTER A.5, PAGE 3-4, 1968).

D-5

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-16 SHEET 6 OF 25
NEW ENGLAND DIVISION COMPUTED BY SOA DATE 7/12/80
BRADLEY HUBBARD RES. DAM CHECKED BY eb DATE 7/14/80

Q₃ = CLH^{3/4} C 29 H^{3/4} L = 70'
 = 200 H^{3/4} (CR2L. 1.1)

SIMILARLY RIGHT SIDEWATER Q₄ AND LEFT SIDEWATER Q₅ ARE CALCULATED BY THE SAME METHOD.

OUTLET Q₆ = 0.1 A^{1/2} H^{3/4}
 THE 20' DIAMETER THROUGH THE DAM IS ASSUMED TO BE THE LOW-LEVEL ORIFICE. COEFFICIENT IS 0.6. Q₆ FOR FLOOD AT 312.94 IS ESTIMATED TO BE 40 CFS. ADJUSTING FOR LOSS OF HEAD.

TABLE 1. DISCHARGE RATING (CFS)


| ELEV. | SPILLWAY Q ₁ | DAM Q ₂ | WATER Q ₃ | RIGHT Q ₄ | LEFT Q ₅ | TOTAL Q ₆ |
|-------------------|-------------------------|--------------------|----------------------|----------------------|---------------------|----------------------|
| 311 | 0 | 0 | 0 | 0 | 0 | 0 |
| 311.56 | 93 | 0 | 0 | 0 | 0 | 93 |
| TOP OF DAM-312 | 273 | 0 | 0 | 0 | 0 | 273 |
| 312.2 | 331 | 101 | 0 | 0 | 0 | 432 |
| 1/4 F-312.45 | 390 | 221 | 0 | 0 | 0 | 611 |
| 312.56 | 435 | 317 | 0 | 0 | 0 | 752 |
| 312.75 | 516 | 479 | 0 | 0 | 0 | 995 |
| TEST FLOOD-312.94 | 604 | 621 | 0 | 0 | 0 | 1225 |
| 312 | 631 | 727 | 0 | 0 | 0 | 1358 |
| 313.06 | 651 | 814 | 0 | 0 | 0 | 1465 |
| 313.2 | 725 | 1014 | 0 | 0 | 0 | 1739 |

NOTE: CONSIDERING THE ... CAPACITY OF THE ... THE DISCHARGE CAPACITY OF THE ...

DISCHARGE RATING CURVE FOR TOTAL Q (COMPOSITE) AND SPILLWAY ...

MA 7/12/80
7/14/80

BRADLEY HUBBARD RESERVOIR DISCHARGE RATING CURVES



DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-16 SHEET 8 OF 25
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/12/80
BRADLEY HUBBARD RES. DAM CHECKED BY Ed DATE 11/21/80

DETERMINATION OF PEAK OUTFLOW

SHORTCUT ROUTING OF RESERVOIR

CORPS OF ENGINEERS GUIDELINES' SURCHARGE STORAGE

ROUTING. ALTERNATE METHOD USED.

FOR 1500 CFS (PMF) THE DISCHARGE RATING CURVE GIVES ELV. = 313.04

AND FROM STAGE-STORAGE CURVE FOR THIS ELV.

STORAGE = 77.11 FT.

STORAGE = $73 \times 12 = 876$ FT.

$0.59 \times 14 = 8.26$

$$Q_p = Q_i (1 - \frac{STOR_i}{19})$$

| ① | ② | ③ | ④ | ⑤ |
|-------------------------------------|-------------------------------------|-------------------------------------|--------------------|------------------------|
| STOR. INCHES (1-STOR _i) | STOR. INCHES (1-STOR _i) | STOR. INCHES (1-STOR _i) | Q _p CFS | ELV. FROM STOR. INCHES |
| 19 | 19 | 19 | 1360 | 312.5 |
| 1.75 | 0.91 | 51 | 1320 | 313.06 |
| 2.32 | 0.88 | 73 | 1305 | 313.24 |
| 2.5 | 0.87 | 79 | | |

COLUMNS ④ & ⑤ ARE ROUNDED TO DISCHARGE RATING CURVE AND

PEAK OUTFLOW = 1320 CFS
 MAXIMUM STAGE = 312.94
 TOP OF DAM = EL. 312.0

∴ THE DAM IS OVERFLOWING BY 0.94 FT.

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-16 SHEET 9 OF 25
NEW ENGLAND DIVISION COMPUTED BY MP DATE 7/12/80
BRADLEY HUBBARD RES. DAM CHECKED BY EL DATE 7/14/80

THE ROUTING IS ALSO DONE FOR $\frac{1}{2}$ PMF

$$\frac{1}{2} \text{ PMF PEAK INFLOW} = \frac{1}{2} \times 1500 = 750 \text{ CFS.}$$

DETERMINATION OF PEAK FLOW -

FOR 750 CFS ($\frac{1}{2}$ PMF) THE DISCHARGE RATING CURVE GIVES
 ELVN = 312.56

FROM STAGE-STORAGE CURVE FOR THIS ELVN = 55 AC·FT.

$$\text{STOR}_i = \frac{55 \times 12}{0.59 \times 1500} = 1.75'' \text{ RUN-OFF}$$

$$Q P_i = Q P_1 \left(1 - \frac{57.4 P_i}{9.5} \right)$$

| ① | ② | ③ | ④ | ⑤ |
|---|---|---|---|---------------------------------|
| STOR, INCHES $\left(1 - \frac{\text{STOR}_i}{9.5} \right)$ | STOR, AC·FT $\frac{12 \times \text{STOR}_i}{9.5}$ | STOR, AC·FT $\frac{12 \times \text{STOR}_i}{9.5}$ | STOR, AC·FT $\frac{12 \times \text{STOR}_i}{9.5}$ | ELVN FROM STORAGE CURVE USING ③ |
| 1.5 | 0.84 | 47 | 630 | 312.3 |
| 1.75 | 0.82 | 55 | 615 | 312.5 |
| 2.00 | 0.79 | 63 | 593 | 312.75 |

COLUMNS ③ & ⑤ ARE PLOTTED ON DISCHARGE RATING CURVE AND

PEAK OUTFLOW Q = 6.1 CFS

MAXIMUM STAGE = 312.45

TOP OF DAM = 12.0

1. THE DAM IS OVERTOPPED BY 0.45 FT

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-16 SHEET 10 OF 25
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/2/80
BRADLEY HUBBARD RES. DAM CHECKED BY ST DATE 11

BREACH ANALYSIS

DOWNSTREAM FAILURE HAZARD -

$$\text{BREAK OUTFLOW } Q_b = \frac{8}{71} \times W_b \times H^{3/2} \times V_s$$

MIDHEIGHT LENGTH: 260' FROM EXISTING DRAWINGS

$$W_b = 40\% \text{ OF MID-HEIGHT LENGTH}$$

$$W_b = 40\% \text{ OF } 260 = 104'$$

HEIGHT OF DOWNSTREAM FAILURE $H = 16.5'$ (POOL AT TOP OF DAM)

PEAK FAILURE OUTFLOW $Q_p = Q_b$ SINCE THE SPILLWAY AND
LOW-LEVEL CREST ARE WITHIN
THE BREACH WIDTH.

$$Q_p = \frac{8}{71} \times 104 \times 16.5^{3/2} \times 1.486$$

$$\text{PEAK FAILURE OUTFLOW} \approx 11,700 \text{ CFS}$$

$$\text{ESTIMATED FAILURE FLOOD DEPTH} = 0.44 H = 0.44 \times 16.5$$

$$\text{IMMEDIATELY DIS OF DAM} = 7 \text{ FT}$$

PERFORM DOWNSTREAM ROUTING OF PEAK FAILURE OUTFLOW
SELECT A SECTION AA 1300' DIS OF THE DAM

USING MANNING'S EQUATION

$$Q = \frac{1.486}{n} \times A \times R^{2/3} \times S^{1/2}$$

$$= 4.4 \times A \times R^{2/3}$$

WHERE $n = 0.07$ AS USED (BRUSH,
STOCKED) BASED ON CHAPTER 5 "OPEN
CHANNEL HYDRAULICS" BY H. A. T. CHOW

$S = 0.043$ ESTIMATED FROM USGS MAP

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-16 SHEET 11 OF 25
NEW ENGLAND DIVISION
BRADLEY HUBBARD RES. DAM COMPUTED BY PCW DATE 11/1/80
CHECKED BY ES DATE 1/1/81

| ELVN | A, SQ. FT | P | R = A/P | R ^{2/3} | Q, CFS |
|------|-----------|-----|---------|------------------|--------|
| 260 | 0 | — | — | — | — |
| 265 | 250 | 101 | 2.48 | 1.83 | 2000 |
| 268 | 640 | 161 | 4 | 2.5 | 7040 |
| 270 | 1000 | 201 | 5 | 2.92 | 12,850 |

STAGE AREA AND STAGE DISCHARGE CURVES ARE PLOTTED FOR SECTION AH

FOR PEAK FAILURE OUTFLOW $Q_P = 11,700$ CFS, ELVN = 269.8 FROM STAGE DISCHARGE CURVE, AND STAGE AREA CURVE GIVES AREA = 970 SQ. FT

$$\text{VOLUME OF REACH } V_1 = \frac{1350 \times 970}{43.530} = 30 \text{ AC. FT.}$$

$$\text{TRIAL } Q_{P_2} = Q_P \left(1 - \frac{V_1}{S}\right), \text{ WHERE } S = \text{TOTAL STORAGE TO TOP OF DAM} = 216 \text{ AC. FT.}$$

$$= 11,700 \left(1 - \frac{30}{216}\right) = 10,100 \text{ CFS}$$

FOR THIS Q_{P_2} THE STAGE DISCHARGE CURVE GIVES ELVN = 269.6

AND AREA: 922 SQ. FT.

$$\therefore V_2 = \frac{1350 \times 922}{43.560} = 29 \text{ AC. FT.}$$

$$\text{RECOMPUTING } Q_{P_2} = 11,700 \left(1 - \frac{30 + 29}{216}\right) = 10,100 \text{ CFS}$$

AND FLOOD STAGE AT SECTION AH = 269.6

$$\text{FLOOD DEPTH AT SECTION AH} = \text{EL. } 269.6 - \text{EL. } 260 = 9.6 \text{ FT.}$$

$$\text{AND VELOCITY AT SECTION AH} = \frac{10,100}{922} = 11 \text{ FPS}$$

SHEET 12 OF 25
MA 7/18/80
EB 7/11/81

BRADLEY HUBBARD RESERVOIR


STAGE AREA CURVE

1350' D/S OF DAM

SECTION A-A

HORIZONTAL DISTANCE IN FEET

LOOKING DOWNSTREAM




SHEET 13 OF 25
MA 7/18/80
EB 7/11/80

BRADLEY HUBBARD RESERVOIR

STAGE DISCHARGE CURVE

DISCHARGE IN CFS
SECTION AA



DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-16 SHEET 14 OF 2
NEW ENGLAND DIVISION COMPUTED BY SEA DATE 7/1/80
BRADLEY HUBBARD RES. DAM CHECKED BY EL DATE 7/1/80

SELECTING A SECTION FOR 600 FT. D. OF SECTION AA

$$Q = \frac{1.486}{n} \times A \times R^{2/3} \times A^{1/2}$$

$$= 5.5 \times A \times R^{2/3}$$

WHERE $n = 0.07$ ASSUMED
 $n = 0.067$ ESTIMATED
 FROM USGS MAP

| EL | A SQ. FT. | P | R = A/P | R ^{2/3} | Q CFS |
|-----|-----------|-----|---------|------------------|-------|
| 220 | 0 | - | - | - | - |
| 225 | 500 | 200 | 2.5 | 1.84 | 5100 |
| 227 | 980 | 280 | 3.5 | 2.30 | 12400 |

STAGE AREA AND STAGE DISCHARGE CURVES ARE PLOTTED
 FOR $Q_1 = 10,100$ CFS, $ELVN = 226.6$ AND FROM
 STAGE CURVE AREA = 918 SQ. FT.

$$VOLUME OF REACH $V_1 = \frac{600 \times 918}{43.550} = 13$ AC. FT.$$

$$STORAGE REMAINING = 215 - \frac{30 + 29}{2} = 186$$
 AC. FT.

$$TRIAL $Q_2 = Q_1 \left(1 - \frac{V_1}{V_2}\right) = 10,100 \left(1 - \frac{13}{186}\right) = 9400$ CFS.$$

FOR 9400 CFS, $ELVN = 226.6$ AND AREA = 871 SQ. FT.

$$V_2 = \frac{600 \times 871}{43.550} = 12$$
 AC. FT.

$$RECOMPUTING $Q_2 = 10,100 \left(1 - \frac{13 + 12}{2 \times 186}\right) = 9,400$ CFS.$$

AND FLOOD STAGE AT SECTION BB = 226.6

$$DEPTH OF FLOOD WATER AT SECTION BB = EL 226.6 - EL 220 = 6.6$$
 FT.

$$VELOCITY AT SECTION BB = \frac{9400}{871} = 11$$
 FPS

SHEET 15 OF 25
MVA 7/18/80
E6 7/11/80


BRADLEY HUBBARD RESERVOIR

STAGE AREA CURVE

1950 FT DIS OF DAM

600 FT DIS OF SECTION AA

ELEVATION IN FEET



HORIZONTAL DISTANCE IN FEET

LOOKING DOWNSTREAM SECTION BB


SHEET 16 OF 25

MA 7/1/80

EB 7/1/80

B RADLEY HUBBARD RESERVOIR
STAGE DISCHARGE CURVE

DISCHARGE IN CFS
SECTION BB



DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-16 SHEET 17 OF 25
NEW ENGLAND DIVISION COMPUTED BY WMA DATE 7/8/80
BRADLEY HUBBARD RES. DAM CHECKED BY EL DATE 7/11/80

SELECT A SECTION CC 500' DIS OF SECTION BB

$$Q = \frac{1.486}{n} \times A \times R^{2/3} \times S^{1/2}$$

$$= 4.00 \times A \times R^{2/3}$$

WHERE $n = 0.05$ ASSUMED
(maintained stream section)
Winding

$S = 0.014$ ESTIMATED FROM SCS MAP

| ELVN | A SQ. FT | P | R = A/P | $R^{2/3}$ | Q CFS |
|------|----------|-----|---------|-----------|--------|
| 211 | 0 | — | — | — | — |
| 215 | 1072 | 535 | 2 | 1.6 | 6,400 |
| 217 | 2370 | 790 | 3 | 2.1 | 19,900 |

STAGE AREA AND STAGE DISCHARGE CURVES ARE PLOTTED.

FOR $Q_1 = 9,400$ CFS. ELVN = 215.8 AND AREA = 1524 SQ FT.

$$\text{VOLUME OF REACH } V_1 = \frac{500 \times 1524}{43.560} \approx 18 \text{ AC} \cdot \text{FT.}$$

$$\text{STORAGE REMAINING} = 186 - \frac{18 + 12}{2} = 174 \text{ AC} \cdot \text{FT.}$$

$$\text{TRIAL } Q_2 = Q_1 \left(1 - \frac{V_1}{S}\right)$$

$$= 9400 \left(1 - \frac{18}{174}\right) \approx 8,400 \text{ CFS}$$

FOR 8,400 CFS - ELVN = 215.5 AND AREA = 1350 SQ FT.

$$V_2 = \frac{500 \times 1350}{43.560} = 16 \text{ AC} \cdot \text{FT.}$$

$$\text{RECOMPUTING } Q_2 = 9,400 \left(1 - \frac{18 + 16}{174}\right) \approx 8,500 \text{ CFS.}$$

AND FLOOD STAGE = 215.5

$$\text{DEPTH OF FLOOD WATER AT SECTION CC} = \text{EL } 215.5 - \text{EL } 211$$

$$= 4.5 \text{ FT.}$$

$$\text{VELOCITY AT SECTION CC} = \frac{8,500}{1350} \approx 6 \text{ FPS}$$

ELEVATION IN FEET

D-18

SHEET 18 OF 25

MA 7/18/20


EB 7/11/20

BRADLEY HUBBARD RESERVOIR

STAGE AREA CURVE

2450 FT DIS OF DAM

500 FT DIS OF SECTION BB



HORIZONTAL DISTANCE IN FEET

LOOKING DOWNSTREAM

SECTION CC

ELEVATION IN FEET

220

215

210

61-D

○

○

○

BRADLEY HUBBARD RESERVOIR

STAGE DISCHARGE CURVE

DATE 7/11/80
BY 7/11/80

24000

20000

16000

12000

8000

4000

0

DISCHARGE IN CFS

SECTION CC

SHEET 19 OF 25

7/11/80

7/11/80

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-16 SHEET 20 OF 25
NEW ENGLAND DIVISION COMPUTED BY CAF DATE 7/1/80
BRADLEY HUBBARD RES. DAM CHECKED BY ED DATE 7/1/80

SELECT A SECTION DD 1350 FT DIS A SECTION CC

$$Q = \frac{1.486}{m} \times A \times R^{2/3} \times V^{1/2} \quad \text{WHERE ... ASSUMPT}$$

$$= 1.8 \times A \times R^{5/3} \quad \text{A} = 0.037 \text{ ESTIMATED FROM LOSS DATA}$$

| EL | A SQ. FT | P | R = A/P | R ^{2/3} | Q CFS |
|-----|----------|-----|---------|------------------|--------|
| 205 | 0 | — | — | — | — |
| 210 | 188 | 76 | 2.41 | 1.83 | 300 |
| 215 | 1000 | 250 | 4.00 | 2.52 | 4500 |
| 218 | 1908 | 356 | 5.36 | 3.06 | 10,500 |

STAGE AREA AND STAGE DISCHARGE CURVES ARE PLOTTED
 FOR $Q_1 = 8,500$ CFS. $EL = 217.4$ AND AREA = 1700 SQ. FT.
 VOLUME OF REACH = $\frac{1350 \times 1700}{40 \times 60} = 53 \text{ AC. FT.}$

$$\text{STORAGE REMAINING} = 174 - \frac{18 + 16}{2} = 157 \text{ AC. FT.}$$

$$\text{TRIAL } Q_2 = Q_1 \left(1 - \frac{V_1}{L}\right) = 8,500 \left(1 - \frac{53}{157}\right) = 5,600 \text{ CFS}$$

FOR 5,600 CFS. $EL = 215.8$ AND AREA = 1218 SQ. FT.
 $V_2 = \frac{1350 \times 1218}{11256} = 38 \text{ AC. FT.}$


$$\text{RECOMPUTING } Q_2 = 8,500 \left(1 - \frac{38 + 53}{2}\right) = 6,000 \text{ CFS}$$

AND FLOOD STAGE 216

DEPTH OF FLOOD IN 11 SECTION DD = $EL 216 - EL 205 = 11 \text{ FT.}$

$$\text{VELOCITY AT SECTION DD} = \frac{6,000}{1260} = 5 \text{ FPS}$$

ELEVATION IN FEET



BRADLEY HUBBARD RESERVOIR

STAGE AREA CURVE

3800 FT DIS OF DAM

1350 FT DIS OF SECTION CC

SHEET 21 OF 25

MA 7/12/80

EB 7/11/80

HORIZONTAL DISTANCE IN FEET

LOOKING DOWN STREAM SECTION DD

D-21

SHEET 22 OF 25

MA 18/80

EB 7/11/82


BRADLEY HUBBARD RESERVOIR

DISCHARGE RATING CURVE

SECTION DD

DISCHARGE IN CFS

ELEVATION IN FEET



D-22

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-16 SHEET 23 OF 25
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/11/80
BRADLEY HUBBARD RES. DAM CHECKED BY EB DATE 7/11/80

FAILURE HAZARD POTENTIAL
SUMMARY OF BREACH ANALYSIS RESULTS

| LOCATION | DISTANCE FROM PEAK FLOW DAM - FT | RAVE CFS | FLOOD STAGE FT. | FLOOD DEPTH FT. | VELOCITY FPS | STORAGE VOL. REMAINING ACFT. |
|----------|-------------------------------------|----------|--------------------|--------------------|-----------------|---------------------------------|
| DAM | 0 | 11,700 | 302.5 | 7 | - | 216 |
| AA | 1350 | 10,100 | 269.6 | 9.6 | 11 | 186 |
| BB | 1950 | 9,400 | 226.6 | 6.6 | 11 | 174 |
| CC | 2450 | 8,500 | 215.5 | 4.5 | 6 | 157 |
| DD | 3800 | 6,000 | 216 | 11 | 5 | 112 |

A FLOOD OF THIS MAGNITUDE WOULD IMPACT GEECKE HUNTER GOLF COURSE. AT LEAST TWO HOMES, WESTFIELD ROAD AND THREE CULVERTS DOWNSTREAM. THE SERIOUSNESS OF THE IMPACT IS DISCUSSED BELOW. THE DEPTH OF FLOOD WATER AT DAM FAILURE IS ESTIMATED TO BE IN THE RANGE OF 1 FT. TO 9.6 FT. BETWEEN THE DAM AND SECTION AA 1350 FT. DOWNSTREAM WITH VELOCITIES IN THE 11 FPS RANGE, AND WOULD THEREFORE DAMAGE THE CULVERT LOCATED 400 FT. BELOW THE DAM AT AN ACCESS ROAD TO THE DAM SITE AS WELL AS INUNDATE WESTFIELD ROAD.

SECTION BB IS TAKEN AT THE EASTERN EDGE OF THE GOLF COURSE ADJACENT TO A CULVERT. AT THIS SECTION THE FLOOD DEPTH IS ESTIMATED TO BE 6.6 FT. WITH A VELOCITY OF 11 FPS; HENCE THE CULVERT AND THE ROAD WOULD BE DAMAGED.

SECTION CC IS TAKEN AT THE CENTER OF THE GOLF COURSE WHERE THE FLOOD DEPTH IS ESTIMATED TO BE 4.5 FT. WITH A VELOCITY OF 6 FPS AND AT SECTION DD TAKEN 100 FT. FROM THE SOUTHERN EDGE OF THE GOLF COURSE ADJACENT TO A HOME ON WESTFIELD ROAD. THE FLOOD

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-16 SHEET 24 OF 25
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/11/80
BRADLEY HUBBARD RES. DAM CHECKED BY EL DATE 7/11/80

DEPTH IS ESTIMATED TO BE 11 FT. WITH A VELOCITY OF 5 FPS. THUS, A SIGNIFICANT PORTION OF THE GOLF COURSE WOULD BE INUNDATED WITH FLOOD WATER THIS ACTIVE GOLF COURSE IS CONSIDERED AS INITIAL IMPACT AREA.

THE HOUSE NORTH OF WESTFIELD RD. AND ADJACENT TO SECTION DD HAS A 1ST FLOOR ELEVATION OF $7.6 \pm$ FT. ABOVE CHANNEL BED AND THEREFORE WOULD BE INUNDATED WITH $3.4 \pm$ FT. OF WATER. SIMILARLY, THE HOUSE LOCATED SOUTH OF WESTFIELD RD. WOULD BE INUNDATED WITH $2.2 \pm$ FT. OF WATER, SINCE ITS 1ST FLOOR ELEVATION IS $8.8 \pm$ FT. ABOVE CHANNEL BED. IN ADDITION, A PORTION OF WESTFIELD ROAD WOULD BE INUNDATED WITH $2.5 \pm$ FT. OF WATER. THESE TWO HOMES AND WESTFIELD RD. ARE CONSIDERED SECONDARY IMPACT AREA.

AT THE END OF FLOOD ROUTING ANALYSIS, 112 AC.FT. OF STORAGE VOLUME IS REMAINING AND ONLY 48% OF THE TOTAL STORAGE VOLUME HAS BEEN ATTENUATED. THUS, THE REACH FURTHER DOWNSTREAM INCLUDING BALDWIN'S POND COULD BE IMPACTED AND IT IS SUGGESTED THAT THIS POTENTIAL IMPACT AREA SHOULD BE INCLUDED IN A FUTURE PHASE II INVESTIGATION.

BASED ON THE ABOVE ANALYSIS, A HAZARD POTENTIAL OF HIGH MAGNITUDE IS CONSIDERED LIKELY.

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-16 SHEET 25 OF 25
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/14/80
BRADLEY HUBBARD RES. DAM CHECKED BY EB DATE 7/15/80

SUMMARY- HYDRAULIC/HYDROLOGIC COMPUTATIONS

TEST FLOOD PEAK INFLOW PMF

1500 CFS

(PARALLEL COMPUTATIONS HAVE BEEN PERFORMED FOR $\frac{1}{2}$ PMF
 PEAK INFLOW AND RESULTS ARE SUMMARIZED BELOW)

PERFORMANCE AT PEAK FLOOD CONDITIONS:

| | PMF | $\frac{1}{2}$ PMF |
|---|------|-------------------|
| PEAK INFLOWS CFS | 1500 | 750 |
| PEAK OUTFLOWS CFS | 1325 | 620 |
| SPILL.CAP. TO TOP OF DAM (EL.312 NGVD) CFS | 223 | 223 |
| SPILL.CAP. TO TOP OF DAM % OF PEAK OUTFLOW | 17 | 36 |
| SPILL. CAP. TO PEAK FLOOD ELEVN. CFS | 604 | 390 |
| SPILL. CAP. TO PEAK FLOOD ELVN. % OF PEAK OUTFLOW | 46 | 63 |

PERFORMANCE:

| | | |
|---|--------|--------|
| MAXIMUM POOL ELEVN NGVD | 312.94 | 312.45 |
| MAX. SURCHARGE HEIGHT ABOVE SPILL.CREST FT. | 1.94 | 1.45 |
| DAM OVERTOPPED FT. | 0.94 | 0.45 |

DOWNSTREAM FAILURE CONDITIONS:

| | |
|---|-----------|
| PEAK FAILURE OUTFLOW CFS | 11,700 |
| FLOOD DEPTH IMMEDIATELY D/S FROM DAM | 7 FT |
| CONDITIONS AT THE INITIAL IMPACT AREA (MIDDLE OF GOLF COURSE AT CC) THE CONDITIONS VARY FROM SECTION BB TO SECTION DD. | |
| ESTIMATED STAGE BEFORE FAILURE WITH 223 CFS | 211.2NGVD |
| ESTIMATED STAGE AFTER FAILURE WITH 8,500 CFS | 215.5NGVD |
| ESTIMATED RAISE IN STAGE AFTER FAILURE ΔY_1 | 4.3FT |
| CONDITIONS AT THE SECONDARY IMPACT AREA: | |
| ESTIMATED STAGE BEFORE FAILURE WITH 223 CFS (AT SECTION DD) | 208.1NGVD |
| ESTIMATED STAGE AFTER FAILURE WITH 6000 CFS | 216. NGVD |
| ESTIMATED RAISE IN STAGE AFTER FAILURE ΔY_2 | 7.9FT |

PRELIMINARY GUIDANCE
FOR ESTIMATING
MAXIMUM PROBABLE DISCHARGES
IN
PHASE I DAM SAFETY
INVESTIGATIONS

New England Division
Corps of Engineers

March 1978

MAXIMUM PROBABLE FLOOD INFLOWS
NED RESERVOIRS

| <u>Project</u> | <u>Q</u> (cfs) | <u>D.A.</u> (sq. mi.) | <u>MPF</u> cfs/sq. mi. |
|-----------------------|-------------------|--------------------------|---------------------------|
| 1. Hall Meadow Brook | 26,600 | 17.2 | 1,546 |
| 2. East Branch | 15,500 | 9.25 | 1,675 |
| 3. Thomaston | 158,000 | 97.2 | 1,625 |
| 4. Northfield Brook | 9,000 | 5.7 | 1,580 |
| 5. Black Rock | 35,000 | 20.4 | 1,715 |
| 6. Hancock Brook | 20,700 | 12.0 | 1,725 |
| 7. Hop Brook | 26,400 | 16.4 | 1,610 |
| 8. Tully | 47,000 | 50.0 | 940 |
| 9. Barre Falls | 61,000 | 55.0 | 1,109 |
| 10. Conant Brook | 11,900 | 7.8 | 1,525 |
| 11. Knightville | 160,000 | 162.0 | 987 |
| 12. Littleville | 98,000 | 52.3 | 1,870 |
| 13. Colebrook River | 165,000 | 118.0 | 1,400 |
| 14. Mad River | 30,000 | 18.2 | 1,650 |
| 15. Sucker Brook | 6,500 | 3.43 | 1,895 |
| 16. Union Village | 110,000 | 126.0 | 873 |
| 17. North Hartland | 199,000 | 220.0 | 904 |
| 18. North Springfield | 157,000 | 158.0 | 994 |
| 19. Ball Mountain | 190,000 | 172.0 | 1,105 |
| 20. Townshend | 228,000 | 106.0(278 total) | 820 |
| 21. Surry Mountain | 63,000 | 100.0 | 630 |
| 22. Otter Brook | 45,000 | 47.0 | 957 |
| 23. Birch Hill | 88,500 | 175.0 | 505 |
| 24. East Brimfield | 73,900 | 67.5 | 1,095 |
| 25. Westville | 38,400 | 99.5(32 net) | 1,200 |
| 26. West Thompson | 85,000 | 173.5(74 net) | 1,150 |
| 27. Hodges Village | 35,600 | 31.1 | 1,145 |
| 28. Buffumville | 36,500 | 26.5 | 1,377 |
| 29. Mansfield Hollow | 125,000 | 159.0 | 786 |
| 30. West Hill | 26,000 | 28.0 | 928 |
| 31. Franklin Falls | 210,000 | 1000.0 | 210 |
| 32. Blackwater | 66,500 | 128.0 | 520 |
| 33. Hopkinton | 135,000 | 426.0 | 316 |
| 34. Everett | 68,000 | 64.0 | 1,062 |
| 35. MacDowell | 36,300 | 44.0 | 825 |

AD-A143 342

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
BRADLEY HUBBARD RESER. (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV SEP 80

2/2


UNCLASSIFIED

F/G. 13/13

NL



| |
|-------|
| END |
| DATE |
| FILED |
| 9-84 |
| DTIC |




MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

MAXIMUM PROBABLE FLOWS
BASED ON TWICE THE
STANDARD PROJECT FLOOD
(Flat and Coastal Areas)

| <u>River</u> | <u>SPF</u> (cfs) | <u>D.A.</u> (sq. mi.) | <u>MPF</u> (cfs/sq. mi.) |
|-------------------------|---------------------|--------------------------|-----------------------------|
| 1. Pawtuxet River | 19,000 | 200 | 190 |
| 2. Mill River (R.I.) | 8,500 | 34 | 500 |
| 3. Peters River (R.I.) | 3,200 | 13 | 490 |
| 4. Kettle Brook | 8,000 | 30 | 530 |
| 5. Sudbury River. | 11,700 | 86 | 270 |
| 6. Indian Brook (Hopk.) | 1,000 | 5.9 | 340 |
| 7. Charles River. | 6,000 | 184 | 65 |
| 8. Blackstone River. | 43,000 | 416 | 200 |
| 9. Quinebaug River | 55,000 | 331 | 330 |

ESTIMATING EFFECT OF SURCHARGE STORAGE ON MAXIMUM PROBABLE DISCHARGES



STEP 1: Determine Peak Inflow (Q_{p1}) from Guide Curves.

STEP 2: a. Determine Surcharge Height To Pass " Q_{p1} ".

b. Determine Volume of Surcharge ($STOR_1$) In Inches of Runoff.

c. Maximum Probable Flood Runoff In New England equals Approx. 19", Therefore:

$$Q_{p2} = Q_{p1} \times \left(1 - \frac{STOR_1}{19}\right)$$


STEP 3: a. Determine Surcharge Height and " $STOR_2$ " To Pass " Q_{p2} "

b. Average " $STOR_1$ " and " $STOR_2$ " and Determine Average Surcharge and Resulting Peak Outflow " Q_{p3} ".

MAXIMUM PROBABLE FLOOD PEAK FLOW RATES

x 5 - NED DAM IDENTIFICATION

⊗ 7' - TWICE SPF AT INDICATED SITES
DEC. 1977



SURCHARGE STORAGE ROUTING SUPPLEMENT

**STEP 3: a. Determine Surcharge Height and
"STOR₂" To Pass "Q_{p2}"**

**b. Avg "STOR₁" and "STOR₂" and
Compute "Q_{p3}".**

**c. If Surcharge Height for Q_{p3} and
"STOR_{AVG}" agree O.K. If Not:**

**STEP 4: a. Determine Surcharge Height and
"STOR₃" To Pass "Q_{p3}"**

**b. Avg. "Old STOR_{AVG}" and "STOR₃"
and Compute "Q_{p4}"**

**c. Surcharge Height for Q_{p4} and
"New STOR_{AVG}" should Agree
closely**

SURCHARGE STORAGE ROUTING ALTERNATE

$$Q_{p2} = Q_{p1} \times \left(1 - \frac{\text{STOR}}{19} \right)$$


$$Q_{p2} = Q_{p1} - Q_{p1} \left(\frac{\text{STOR}}{19} \right)$$

FOR KNOWN Q_{p1} AND 19" R.O.


Q_{p2}

STOR

EL.



"RULE OF THUMB" GUIDANCE FOR ESTIMATING DOWNSTREAM DAM FAILURE HYDROGRAPHS



STEP 1: DETERMINE OR ESTIMATE RESERVOIR STORAGE (S) IN AC-FT AT TIME OF FAILURE.

STEP 2: DETERMINE PEAK FAILURE OUTFLOW (Q_{p1}).

$$Q_{p1} = \frac{8}{27} W_b \sqrt{g} Y_0^{3/2}$$

W_b = BREACH WIDTH - SUGGEST VALUE NOT GREATER THAN 40% OF DAM LENGTH ACROSS RIVER AT MID HEIGHT.

Y_0 = TOTAL HEIGHT FROM RIVER BED TO POOL LEVEL AT FAILURE.

STEP 3: USING USGS TOPO OR OTHER DATA, DEVELOP REPRESENTATIVE STAGE-DISCHARGE RATING FOR SELECTED DOWNSTREAM RIVER REACH.

STEP 4: ESTIMATE REACH OUTFLOW (Q_{p2}) USING FOLLOWING ITERATION.

A. APPLY Q_{p1} TO STAGE RATING, DETERMINE STAGE AND ACCOMPANYING VOLUME (V_1) IN REACH IN AC-FT. (NOTE: IF V_1 EXCEEDS $1/2$ OF S, SELECT SHORTER REACH.)

B. DETERMINE TRIAL Q_{p2} .

$$Q_{p2}(\text{TRIAL}) = Q_{p1} \left(1 - \frac{V_1}{S}\right)$$

C. COMPUTE V_2 USING $Q_{p2}(\text{TRIAL})$.

D. AVERAGE V_1 AND V_2 AND COMPUTE Q_{p2} .

$$Q_{p2} = Q_{p1} \left(1 - \frac{V_{\text{avg}}}{S}\right)$$

STEP 5: FOR SUCCEEDING REACHES REPEAT STEPS 3 AND 4.

APRIL 1978

APPENDIX E

INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS

NOT AVAILABLE AT THIS TIME

ATE
LME